

**A SUSTAINABILITY CHARTER
FOR
VICTORIA PARK, DENTON**

A sustainability Charter for Victoria Park, Denton

Tameside Council is committed to the principles of sustainable development and is striving to improve the quality of life of those living, working and visiting the area both now and in the future. Through the provision of services it aims to contribute to the objectives of the UK Strategy for Sustainable Development, which seeks to achieve:

Social progress that meets the needs of everyone.

Effective protection of the environment.

Prudent use of natural resources.

Maintenance of high and stable levels of economic growth and employment.

Tameside MBC has produced a 'Quality of Life Strategy' which sets out an action plan to implement the Local Agenda 21 principles. This covers all aspects of the Councils responsibilities including the built environment, the natural environment, waste management and pollution. It is against the background of this strategy that the following guiding principles for Victoria Park have been developed.

Guiding Principles

In its management of the facilities provided at Victoria Park the Council undertakes to:

Reduce the consumption of natural resources, especially energy and water.

Where feasible, substitute non-renewable resources with renewable ones.

Minimise the production wastes.

Reuse and recycle wastes.

Release wastes only in forms which natural processes can assimilate.

Prevent pollution by minimising the use of chemicals.

Preserve and where possible increase the variety and diversity of species and habitats.

Protect natural and built up physical assets and amenities that once damaged would be impossible, difficult or very slow to restore and recreate.

Encourage sustainable modes of travel to and from the park.

Ensure all facilities are accessible to all members of the public.

Maintain a clean, safe and secure environment.

Establish mechanisms for continual liaison with users of the park.

**PLAYGROUND INSPECTION
SHEETS**

VICTORIA PARK, DENTON – Health & Safety Inspection Sheet & Fault Report

Inspected By: _____

Week Ending: _____

Weather Condition: _____

If Snow on Ground Please State:

Fault Report:
(See Opposite Plan)

Details: _____

Reported To: _____

Date: _____

		M	T	W	Th	F
A	Picnic Bench					
B	Picnic Bench					
C/J	Sandpit					
C/a	Train/ diggers					
D	Springy Bike					
E	Springy Bird					
F	Sound Tube					
G	Bike Roundabout					
H	Seesaw					
I	Sound Tube					
J	Climbing Frame & Slide					
K	Double Swings					
L	Swings					
M	Climbing Frame (New)					
N	Climbing Frame (Old)					
	Toddlers Fencing/ Gates					
	Benches/ Bins					

Perimeter Fencing & Gates

Side 1					
Side 2					
Side 3					
Side 4					

Litter

General Litter					
Broken Glass					
Syringes					
Cat/ Dog Waste					
Fly Tipping					

For Play Unit Use

Actioned By: _____

Date: _____


Details: _____

Graffiti on Item

A	B	C	D	E	F
G	H	I	J	K	L
M	N	O	P	Q	R
P	Q	R	S	T	
1	2	3	4		

Please Circle

VICTORIA PARK, DENTON



District Assembly Service - Criminal Damage Reporting Sheet

LOCATION:	
POST CODE:	
DISTRICT ASSEMBLY AREA:	
DATE OF OFFENCE:	
DESCRIPTION OF DAMAGE:	
PROPERTY TYPE:	
CRIME NUMBER:	
APPROX. COST OF DAMAGE:	

Completed by:

Date:

Added to Database:	
---------------------------	--

Please include damage to buildings, street furniture, floral displays, trees/saplings, shrubs, vehicles or machinery, bowling greens, grassed areas, play equipment etc.

Return the completed form to ian.cochrane2@tameside.gov.uk

District Assembly Service - Criminal Damage Reporting Sheet

LOCATION:	Victoria Park, Denton
POST CODE:	M34 2AP
DISTRICT ASSEMBLY AREA:	Denton & Audenshaw
DATE OF OFFENCE:	1 st April 2007
DESCRIPTION OF DAMAGE:	Graffiti over the mural in Victoria Park (rear of Denton Swimming Baths)
PROPERTY TYPE:	Brick rear wall of swimming baths
CRIME NUMBER:	-
APPROX. COST OF DAMAGE:	£640.00

Completed by: Nick Sayers

Date: 23/04/2007

Added to Database:	Yes - DADA 01
---------------------------	----------------------

Please include damage to buildings, street furniture, floral displays, trees/saplings, shrubs, vehicles or machinery, bowling greens, grassed areas, play equipment etc.

Return the completed form to ian.cochrane2@tameside.gov.uk

District Assembly Service - Criminal Damage Reporting Sheet

LOCATION:	Victoria Park, Denton
POST CODE:	M34
DISTRICT ASSEMBLY AREA:	Denton
DATE OF OFFENCE:	09.07.2007
DESCRIPTION OF DAMAGE:	Playing football on No 1 Bowling Green (turf damage)
PROPERTY TYPE:	Bowling Green
CRIME NUMBER:	173109X – 07
APPROX. COST OF DAMAGE:	£100

Completed by: D Clapham

Date: 11.07.2007

Added to Database:	DADA 02
---------------------------	----------------

Please include damage to buildings, street furniture, floral displays, trees/saplings, shrubs, vehicles or machinery, bowling greens, grassed areas, play equipment etc.

Return the completed form to ian.cochrane2@tameside.gov.uk

District Assembly Service - Criminal Damage Reporting Sheet

LOCATION:	Victoria Park, Denton
POST CODE:	
DISTRICT ASSEMBLY AREA:	Denton & Audenshaw
DATE OF OFFENCE:	21 st July
DESCRIPTION OF DAMAGE:	Graffiti on bandstand & mural
PROPERTY TYPE:	Park
CRIME NUMBER:	-
APPROX. COST OF DAMAGE:	£120

Completed by:

Date:

Added to Database:	
---------------------------	--

Please include damage to buildings, street furniture, floral displays, trees/saplings, shrubs, vehicles or machinery, bowling greens, grassed areas, play equipment etc.

Return the completed form to ian.cochrane2@tameside.gov.uk

MAN'S BEST FRIEND... LET'S KEEP IT THAT WAY!

Dog fouling

doesn't just make
Tameside's streets and
parks look filthy.

Not cleaning up after your
dog could cost you a **£50**
spot fine. This could rise to
a **£1,000** penalty in court
if you don't comply.

Dog mess is dangerous too
– It contains germs that can
cause blindness.

Be sure to clean up after
your pet!

PICK IT UP



OR PAY UP

 **Tameside**
Metropolitan Borough
141 Market Street

**Victoria Park Action Plan
2007 – 2009**

WORK IDENTIFIED	COMMUNITY STRATEGY						COMPLETION DATE			APPROXIMATE COST
							2006/ 2007	2007/2008	2008/2009	
	Attractive Borough	Safe Environment	Supportive Communities	Healthy Population	Prosperous Society	Learning Community				
<u>A Welcoming Place</u>										
Replace existing notice boards							Completed			£1,500.00
Improve entranceway landscaping, Acre Street							✓	✓		£500.00
<u>Healthy, Safe & Secure</u>										
Install Playground Equipment							Completed			£10,000.00
Prepare Capital Bid for major works							✓	✓	✓	-
Undertake tree works as required							✓	✓	✓	-
Carry out Sports area improvement							Completed			£30,000.00
Repair damaged path surface							✓	✓	✓	£30,000.00
<u>Clean & Well Maintained</u>										
Renew Bowling Green boards							✓	✓	✓	£400.00 pa
Look at alternative areas to store waste							✓	✓		£3,000.00
Arrange new men's bowling pavilion							✓	✓		£26,000.00
<u>Sustainability</u>										
Naturalised bulb planting							Completed			£250.00
<u>Conservation & Heritage</u>										
Carry out renovation works to bandstand							Completed			£90,000.00
Install heritage style park furniture							✓	✓	✓	£6,000.00
Bandstand floor surface							✓	✓	✓	-
Monitoring use of the bird/ bat boxes							✓	✓	✓	-
Submit Heritage Site Application							✓	✓	✓	-
War Memorial Annual Survey							✓	✓	✓	
Install Interpretation Boards							Completed			£2,000.00

WORK IDENTIFIED	COMMUNITY STRATEGY						COMPLETION DATE			APPROXIMATE COST
	Attractive Borough	Safe Environment	Supportive Communities	Healthy Population	Prosperous Society	Learning Community	2006/ 2007	2007/2008	2008/2009	
Community Involvement										
Explore potential for developing Victoria Park Community Centre to provide not-for-profit community and catering facilities for park users							✓	✓		
Develop events programme							✓	✓	✓	£1,800.00 pa
Continue to support the Friends Group							✓	✓	✓	-
Arrange annual Brass Band Concerts							✓	✓	✓	£2,000.00
Develop events programme with Sports Development							✓	✓	✓	-
Provide Teachers Packs to Local Schools							Completed			£2,500.00
Marketing										
Produce marketing information							✓	✓		-
Management										
Review Management Plan							✓	✓		-



Denton & Audenshaw District Assembly



Victoria Park Conservation Plan



<u>Contents</u>	<u>Page</u>
1. Introduction	61
2. The History and Heritage of Victoria Park (Denton Park)	61
• Lost features with in Victoria Park	68
• Surviving features of Victoria Park	70
• Memories of Victoria (Denton Park)	84
3. The Management of Victoria park	87
4. Victoria Parks Community Use and Enjoyment	91
5. Conclusion	96

1. Introduction


In May 2007 Tameside Metropolitan Borough Council, Denton & Audenshaw District Assembly received confirmation from the Heritage Lottery Fund that its application for a grant to restore the bandstand in Victoria Park, Denton had been successful. This gave the opportunity to consider Victoria Parks heritage, how we can preserve the present features and restore historical elements to the park once again. The Green Heritage Site Award would help recognise this and the contribution that local community groups and the public have made in the restoration of Victoria Park.

2. The History and Heritage of Victoria Park (Denton Park) Playing Fields and Recreation Ground


Victoria Park was opened officially in 1913 on land which had been bought in 1886. The Park originally had a number of features which have been lost over the years including a children's paddling pool, a drinking fountain and a stone archway at the entrance to the bowling greens. Fortunately other features such as the bandstand, bowling green and flower gardens have been retained to the present day. The war memorial originally unveiled on July 23rd 1921 also remains as an important feature of today's park.

In common with many other urban parks across Britain, Victoria Park suffered a decline in its appearance over of period of time. However, in recent years work has been undertaken to halt this pattern and improve the condition of the park. Recognition of this was the award in 2000 of the park's first Green Flag, which served not only to note what had been achieved but more importantly to form a base from which to move forward and improve this important and popular local park still further.

The recreation grounds between Victoria and Acre Streets were opened on Whit Friday, June 14th 1889 by Mr Lees Broadbent and Mr Jonathan Moores. The events leading up to the opening have been recorded in detail as follows: At the annual meeting of ratepayers held in the old church (St Lawrence) not only were the constables, surveyors and overseers elected but, as village life expanded, the town's meeting also elected a committee of management called a Board, empowered to perform the functions of local government for a year and usually meeting monthly in St Lawrence's School. The neighbouring township of Haughton had its own Board but, in 1884, the townships of Denton & Haughton were amalgamated under one authority as 'The Denton & Haughton Local Board'.




The proposed land on which the park stands was formerly part of the Woodiwis Estate, it was bought on 1st May 1886 at a cost of £6,750 and measured 40,535 square yards. A scheme of alterations to the Recreation Grounds included the enclosure of strips of land along Victoria Street and Acre Street as part of the Grounds and provision made for a bandstand, fountain and bowling green. The execution of the work extended over 7 years from 1907 to 1913. The map above is a 1918 OS Map of Victoria Park.



The aerial photograph above was taken in the 1930s and shows the full extent of Victoria Park at that time. Acre Street runs from bottom left to right and Victoria Street is to the left of the park. No. 1 and No. 2 bowling greens are clearly visible at the top of the picture and the original tennis courts are at the bottom of the photograph.

The map below is a 1904 - 1939 Victoria Park OS Map overlaid with the 2007 Victoria Park OS Map highlighted in red, showing how little the layout of the park has changed in over a 100 years.



Byelaws

Denton Urban District Council made byelaws (Section 164 of the Public Health Act 1875) in respect of PLEASURE GROUNDS including Victoria Park, some of which by today's standards may seem strange, examples of which are as follows:

Cattle, sheep, goats or pigs, or any beast of draught or burden are not allowed in the park unless authorised.

A person shall not in the pleasure ground hang, spread, or deposit any linen or other fabric for drying or bleaching.

The opening ceremony : Denton and Haughton Recreation Ground - Presentation of Gold Keys

The extracts below are taken from the Ashton Reporter, 22nd June 1889

The local Board, being ready to do their best for the rising generation, have made a recreation ground out of their estate near The Free Library (Town Hall). The surveyor, Mr Wharam, managed the project. The playground is divided into two portions for boys and girls. The whole is fenced round with un-climbable railings and has two entrances. Swings, gymnasts, etc, including a little sand bed for the children in the girls' portion are provided without stint. The opening of the ground took place on Whit Friday, 1889.

A meeting of the Board was first held in the Board Room, Market Place, the object being to present Mr Lees Broadbent (the Chairman of the Board) and Mr Jonathan Moores (Chairman of the Market and Building Committee) each with a gold key, with which to open the gates. One key was engraved with the words "Presented to Lees Broadbent Esq C.C. on the occasion of the opening of the Denton and Haughton Public Playground, 14th June 1899". The key presented to Jonathan Moores carried a similar inscription. The reverse side of the handle contained the Denton Coat of Arms and the following inscription "Denton 1857, Haughton 1877. The Denton and Haughton Local Board AD 1884". The gentlemen present included Messrs Broadbent, Howe, M Taylor, Hyde, Moores, Trubshaw, Blackshaw, Woolfenden, Cooke, Walker, Rothwell, Richards (Clerk), Veevers and G Taylor.

The company proceeded to the playground, the two gates unlocked and the playground declared open. The gentlemen now walked to the platform, which had been fixed in the centre, to await the arrival of the children from the Sunday Schools. The weather was not very bright but, fortunately no rain fell and, as the scholars marched on the ground to their allotted places, the scene was picturesque in

the extreme. Mr John Richards announced the proceedings and Mr Broadbent, who was received with loud cheers, said the Board had great pleasure in dedicating the ground for their use.

The Denton Original Band struck up the "Old Hundredth", and the proceedings concluded with the singing of the National Anthem.

Staff in the park.

A considerable number of gardeners and park keepers have been employed since the war and prominent amongst these are Harold Johnson, J Clark, Harold Hansford and Peter Ebbrell (late 1960s to 1974). Park keepers working in shifts included Jack Atkinson, Mr Pearson and Mr Fishwick. Ken Ridley worked from the 1960s through to his retirement. Bernard Pedley became Head Gardener having worked in the Parks and Cemeteries Department for almost 40 years.

In the 1960s, Ken Ridley was a gardener in Denton Park working for the local council, the Council had to pay £10 per day to hire a tining machine. Due to the cost, Ken worked late into the evening to finish the job and to enable him to see what he was doing (as darkness fell) he fixed bicycle lamps on to the machine. This drew the attention of the local police who came along to the scene and were duly relieved to see that it was Mr Ridley doing his job with homemade floodlights.



The photograph above shows gardeners working in the park in 1918.

Then there were three greenhouses on the east side of the park – where the OAP Centre (now renamed the Victoria Park Community Association) and police compound are today. They were heated by boilers. The centre one was the tropical house where bananas were grown. The two on either side were used for growing and hardening off bedding plants. The greenhouses were demolished in the early 1970s and plants are now supplied from Denton Cemetery Road nurseries



Ruth Robinson, now a Project Support Officer in the Town Manager's Office, previously worked as a gardener in Victoria Park. In the photograph, Ruth can be seen tending one of the flower beds.

An imposing list of gentlemen responsible for the park management includes Mr Gowdrige who was the Park Superintendent and Registrar of Denton during the 1950s. He was followed by Mr Ernest Horrobin who held similar positions from 1960 to 1974.



Mr Gowdrige



Mr Horrobin

In 1974, Tameside was created and Mr Edward Neighbour became Chief recreational Officer, others included Mr Holland and Mr McBurney. In the 1990s, Paul Lawday followed as Director of Leisure Services until District Assemblies were formed who then assumed responsibility for the parks. The General Manager was Colin Fielding and Andrew Mason is now Assistant Executive Director of the District Assemblies, Stuart Mollison became first Denton & Audenshaw District Assembly Town Manager.

Lost Features with in Victoria Park

A number of features have existed in the park, some of which have survived but sadly one or two have had to be dismantled for safety reasons, these include-



The Stone Arch

Was constructed in 1926 from marble rockery stones and formed an impressive feature near to the Bowling Greens but was unfortunately demolished in the 1980s after being left to become dangerous. The photograph above was taken in 1935 and shows Mr William Jackson Fraser passing through the archway towards the Bowling Green – probably to watch his grandson, Jim Stafford, playing in a championship bowling match.

The Water Feature

Shown in the photograph below was particularly ornate and at one time had a double pathway around its perimeter. The feature was demolished and landscaped into one of the largest flower beds in Tameside. Also in the photograph of the water feature is a floral archway which was another outstanding feature of Victoria Park.



The Drinking Fountain

Seen in the photograph below was another ornate feature of the park. With the availability of cleaner water to towns in the mid/late 19th century, drinking fountains were built in public places. Denton Park had its own fountain which was stepped all round to enable easy access to the metal cups used at the fountain. There was an extra step on one side to allow children to reach the tap. Sadly the fountain was closed in the 1950s and eventually dismantled and the mark of its base can be seen in the pathway approaching the bandstand.



Public toilets

Stood in the area next to the swimming baths.

The Brick Bowling Shelter

This small building stood near to the corner of No. 1 bowling green and was built before the last war. The view shows the open side of the shelter which contained all round seating. The opposite side contained a small room in which the bowling equipment was stored. It was demolished in 1993. Next to the bowling shelter stood the Tennis Club hut which was demolished in the late 1970s.



Surviving Features of Victoria Park

Playground Area

The children's playground first featured in the early 1900s as a playing area and has been located in several places in the park. Its present site lies along Acre Street, as shown in the photograph below, after refurbishment in 2006.



The photograph below shows the Victoria Park playground in the early 1950s. In the foreground, children are sitting on a rocking horse and in the distance can be seen a typical "Plank Swing". In the centre of the photo is a paddling pool installed in 1931 together with a Merry-go-round Ocean Wave, a Plank Swing, set of Parallel Bars and a 5-seater Rocking Horse. The cost, estimated at £320 was met by the Carnegie Trustees.



The coloured photo below shows a rather more sedate 'kiddies' roundabout' in the early 1970s and was taken in the area now occupied by the Swimming Pool Car Park. The young ladies featured are the daughters of Mrs Joyce Heap, a Local History Society member.



Tennis Courts

Three tennis courts were constructed in the park between 19th November 1919 and March 1920. Two were laid with turf and one with shale. After the 1922 season, the two turf courts were also converted to shale.

Tennis tournaments were played in aid of the Denton Hospital Fund. The prestigious Denton Jubilee Hospital Challenge Cup was presented to the Tennis Section by Mr C H Pinnington in 1935. Harold Lennie won the championship in the park three times. When Harold died, his brother Harry donated the Tennis Cup to the Denton Local History Society to enable future generations to appreciate a small part of the club's history.



Headlines in the sports columns of the Denton Reporter in the late 1930s regularly featured tennis events in Victoria Park and, in particular, highlights of the year including the competition for the Pinnington Cup. The most prominent player at that time was H L Logan winner of the cup in 1936 and 1937. He was the defeated finalist in 1938.

Exhibition matches were also held in the park and the tennis events were always well supported by tennis enthusiasts from all around the area. In the photo over leaf are the winners of the Denton Tennis Tournament in the 1930s.



Winners of Denton Tennis Tournament, staged in July.

The photograph below is Mr Frank Ashton, who was a County tennis champion, umpired many of the local tennis matches. Later he went on to be a first class match umpire at Wimbledon where many famous international players featured including Bjorn Borg, also in the picture.



Bowling Greens

Denton Park Bowling Section started on 4th August 1910 when the No. 1 bowling green was opened, as part of a scheme of alterations to the recreation grounds to provide a bandstand, fountain and public bowling green. The work extended over seven years from 1907 to 1913. The No. 2 green was opened in 1927 and is devoted to the Ladies Bowling Section.

The photograph below was taken in 1912 and shows the entrance to the bowling green as it was at that time.



Mr Whitham Moss, born in 1875, was a renowned local bowler. As a keen and very competitive sportsman he would play for stakes backed by local bookies, never using his own money. He travelled around the area playing in bowling competitions even as far as Blackpool. He loved a challenge and would never fail to accept or give one. Whitham won the Local Hospital Fund Cup three times – once in 1940 at the age of 65. The money raised went into the fund to pay for treatment of the people of Denton. The photograph on the left shows Whitham Moss at the age of 65, in 1940, when he had won the Denton District Hospital Fund Bowling Handicap Cup.

Whitham Moss was a dyer by trade in the hatting industry and worked for Wild & Booth, hat manufacturers. He applied the same dedication to his work as he did to his bowling and was a well respected and valued employee. As a young man he lived in Wild Street which ran behind the Red Lion public house off Hyde Road and, after marriage, resided in Gould Street off Manchester Road. Many people in Denton still remember him to this day.



Mr James Stafford, an aspiring young bowler and grandson of Whitham Moss, had been taught by him from about the age of 8 years. James idolised his grandfather and wanted to follow his footsteps into bowling. In July 1938, aged 21, James won the “Independent Order of the Oddfellows Cup” (the Manchester Unity). There were 80 competitors and the current holder at the time, Mr J M Bromley, another Denton bowler, was defeated in the first round by a Lancashire County Bowler, Mr J Kenyon. Mr Bromley won the Denton Hospital Fund Cup in September 1938. James played for the Bowling Green public house team. Several public houses had excellent bowling green facilities, including the Fletchers Arms, Wilton Arms and the Gentlemen’s Club in Wilton Street. Pub players pursued a more aggressive game whereas the Denton Park players pursued a gentler game – their team consisting of older players. The Denton Hospital Cup was always played for on the Denton Park bowling greens. James is pictured below.



During the war years, most young men were away fighting for King and Country but the older ones, left behind, still managed to get in a little bowling and were always referred to as the Denton Park Veterans or “Owd Fellers”.

In July 1938, for the second successive year, the Denton Park Bowling Club won the Eastern Section of the Manchester Parks Association League. They were undefeated throughout the season and then went forward to compete for the Goldman Cup. The Hon Secretary of the Park Bowling Club was Mr George Follows of the “Park Shelter” or, as some preferred to call it, “Th’owd Fellers Forum”. George wrote to thank several benefactors (via the newspaper) for their generosity:- firstly, for a trip to Belle Vue circus – all expenses paid, also, the renewal of their wireless licence and last but not least for providing seats at the shelter, some of which were the plush seats formerly at the Palace cinema on Ashworth Street, Denton – small pleasures but very much appreciated by all.



This happy group of bowlers from the Ladies Section celebrate the winning of a Bowling Cup in 2000. Making the presentation on the right is May Thompson and the other ladies are Irene Parkin and Irene Layfield. They are standing in front of the portacabin clubhouse which was installed after the original clubhouse was demolished in the early 1950s.

The Bandstand

The Bandstand is a very important structure and well deserves its status of a Grade II Listed Building. Over the years, it has been the means of providing a great deal of pleasure to many local people. Although its appearance and condition have varied between many successive bouts of renovation, it has always remained in regular service and, in recent years, has contributed to the Park's entry in the 'Green Flag Award Scheme'.

The cost of the recent restoration work has been mostly covered by grants from the Government and the Heritage Lottery Fund. Guided by the 'Planning and Historic Environment Document' and with a view to protecting its archaeological heritage, the following rule was laid down in the survey of 2005: All repairs, replacements and materials must be true to the building's original concept, using original methods of construction and components whenever possible. Please see appendices for more details.

The structure was first designed and built by Hill & Smith in their Brierley Hill Foundry in the Midlands. Their 1904 catalogue says it would have an octagonal plinth, wrought/cast iron balustrades attached to cast iron pillars supporting a domed roof with an ornamental weather vane and would be supplied and erected for the sum of £172-10s-0d. Since, however, the very function of the Bandstand is to create a venue for the bands, its story cannot be told without mention of the many bands which have played on it over the years. Although it was not built until the early 1900s, the need for a bandstand existed long before then.

Denton's very first band was formed in 1818 and began playing in public for various celebrations. The townspeople, and especially the hatter Joseph Howard, had subscribed generously to the appeal for funds. They were able to buy a set of instruments, music paper and instruction books for a grand total of £210. The big drum was duly painted with the title 'Haughton & Denton Band'. Haughton, however, was at that time a separate town and the Dentonians, who outnumbered the Haughtonians, objected to this and so the name was eventually changed to 'Denton & Haughton Band'.

Their meeting room was initially at the Masons' Arms, Stockport Road, but in 1837 they moved to the Cock Inn on Two Trees Lane, Haughton. It was a very popular band and played for many years. Until 1869, it led the St Lawrence's Sunday School Scholars' Walk at Whitsuntide. However, since 1859 it had a rival. This was the Baxendale's Band named after their small factory at the top of Taylor Lane. As they went from strength to strength, they had to move their Headquarters; first to the Bowling Green Inn and then to their own Band Institute on Ashton Road. They needed a new name, and so they called themselves the 'Denton Original Band'. This distinguished it from the 'Denton & Haughton Band' and indicated that it was the original 'all Denton band'.

As its popularity grew, it eventually eclipsed its old rival. Its great achievement came in 1900 when it won £75 and the 'One Thousand Guinea Challenge Cup' at Crystal Palace, having competed against entrants from all over Great Britain and the Colonies. There was much rejoicing in Denton at the time and this was the first band to play on our new bandstand in 1913.

The band had many assignments and a new custom had started in 1900. Whenever a member left the band to go and fight for his country, he was given a great 'send-off'. He was marched from his home to Denton Station by the entire band and a procession of well-wishers. The band played patriotic marches and hundreds of people turned out to watch.

In the early 1900s, the hatting industry presented the band with a beautifully crafted mace which was proudly carried by the drum major when marching. The top of the mace was adorned with a model of a bowler hat to symbolize what Denton was famous for. Over the years, the mace led many processions but, alas, the mace is now lost.

By 1919, when they had celebrated their Diamond Jubilee, they were meeting in a dining room at the Market Place but moved later to the King's Head and then in 1973 to Denton Cricket club on Egerton Street. In 1979, following a fire in their band room, the band folded, but from this came the 'Crown Point Band' and the 'Oldham Batteries Band'. The latter name was derived from their venue which was Oldham Batteries' Sports & Social Club but, as some members came from the former band, it soon regained its title of the Denton Original Band. In the 1990s it again re-formed and adopted the title of 'Denton Brass'. This is still with us today and they practise in their room at the Silver Springs Hotel, Ashton Road.


In addition to the local bands, many others from all parts of the UK have played on our bandstand over the years, and still do. They cover all types – such as military bands and especially colliery bands. Before World War II, brass band concerts took place there every Sunday afternoon and evening during the summer months.



Denton Brass Band outside Denton Town Hall about 1910



St John's Band Droylsden playing in Victoria Park on the 16th of September 2006



Denton Original Band in the early 1900s



The Bandstand Opening Event June 16th 2007 with Denton Brass Band

War Memorial

In June 1919 Denton Urban District Council decided to collect the names, addresses, and service details, of all those from the area who had served their country during the Great War. In the weeks that followed enumerators were sent from house to house collecting the names of those who had served. Residents of Denton were also encouraged to write to the council with the details of relatives who had served.

The Denton War Memorial, unveiled on July 23rd 1921 in Victoria Park, Denton, was compiled from the resulting listing.

Fortunately the original notebooks in which the enumerators recorded the names, along with many of the letters received by the Council, have survived. These are now part of the records of Denton UDC, held by the Tameside Archive Service. These have now been transcribed and entered onto a searchable database, which can be accessed by all those endeavouring to find details of Denton`s First World War servicemen.




It is estimated that in 1914 the population of Denton was approximately 17,000, of which just over 8,000 were males. It is also estimated that almost 3,500 Denton men served during the Great War and that of those, 379 lost their lives. This listing comprising approximately 2,500 men is not complete, nor, as with any such listing, is it 100% accurate.



The memorial was constructed by Messrs J. and J. Hirst of Denton, who were also co-designers; the other party being Mr Arnold Radcliffe; the son of Mr Clarence Radcliffe of Radcliffe and Ogden, Silk Hat Manufacturers - one of the towns many hatting firms. Having organised a competition to decide on a design for the memorial, the council proved unable to choose between Hirst and Radcliffe, and the £30 prize was shared between them; parts of both designs being adopted.

Standing 20ft high and weighing 90 tons, the memorial is grey in colour and in the form of a cenotaph. It is fixed into a solid concrete bed more than a yard thick. Four steps lead up to the memorial on four sides. At the front, the dates 1914 and 1918, surrounded by wreathes, are either side of a panel of names. Above, on the central column, it states:

'In grateful and undying remembrance of those who gave their lives in the Great War 1914 - 1918. This memorial has been erected by their fellow townsmen July 1921'



The original bronze plaque with its crossed guns on the front of the memorial sadly was stolen in about 1978 and has never been recovered. A new tablet replaced it.

Names of the fallen on the Denton War Memorial

The Names of the Fallen ☘

Ackley, Harold
 Acton, John
 Adshedd, George W.
 Adshedd, William
 Ainsworth, Frank
 Ainsworth, Herbert
 Ainsworth, William
 Alcock, Joseph
 Anderson, Tempest
 Andrew, Harry
 Andrew, John W.
 Arrandale, Ben
 Artingshall, John A.
 Artingshall, William G.
 Ashley, George
 Aveson, John R.
 Axon, Albert E.
 Bagnall, F. W.
 Bagnall, Harry
 Bagnshaw, Cyril
 Bardsley, Albert
 Bardsley, Edwin
 Barlow, Percy
 Basnett, Joseph
 Basin, Alfred
 Beard, Arthur
 Beard, Joseph
 Beeley, Herbert
 Bedringer.
 Bennett, James
 Bennett, Walter
 Bersford, James
 Berry, Richard
 Beswick, William
 Bilsbury, George E.
 Bims, James
 Birchborough, Harry
 Bird, Arthur
 Birkley, E. Eric
 Blackledge, William G.
 Blackledge, Fred
 Boardman, William E.
 Boon, Ernest
 Booth, William H.
 Booth, Clarence
 Booth, Frank
 Booth, Mark
 Booth, Norman H.
 Booth, William
 Bowden, Jonas
 Bowers, Edwin
 Bradburn, Anthony
 Bradburn, Josiah
 Bradbury, Arnold
 Braddock, Fred
 Braddock, Herbert
 Braddock, Percy
 Bridge, Harold
 Broad, Alfred B.
 Bronsley, Charles
 Bronsley, Percy
 Brook, James A.
 Broom, William
 Brown, William
 Brown, Horace
 Brown, Solomon
 Burgess, Harry
 Burt, William
 Callaghan, Edward
 Carrington, John
 Carter, George
 Carter, Robert
 Carvell, John
 Catlow, Harry
 Catlow, Harry
 Catlow, Hartley P.
 Catlow, Samuel
 Chandler, Joseph H.
 Chandler, Joseph H.
 Chedham, Henry
 Chorlton, William
 Christopher, William
 Clark, Harry
 Clarke, Joshua
 Clayson, Louis
 Cliffe, Peter J.
 Collis, Sydney
 Condon, John
 Cooke, John A.
 Cooke, John W.
 Cooper, Fred
 Cooper, James
 Cooper, Wright
 Costello, John
 Faulkner, Arthur
 Faulkner, James
 Fenn, Harry
 Fernley, Percy
 Fidler, John
 Finkle, James
 Follows, Harry
 Follows, James
 France, Albert
 France, Charles
 France, Harold
 France, John
 Fraser, John R.
 Ganson, Herbert
 Ganson, James
 Gardner, Harry
 Gaskell, Randall
 Gatt Kirk, Albert
 Gee, George
 Gibbons, Harry
 Gibbons, Ralph A.
 Gilbey, Thomas
 Graham, John T.
 Graham, Percy
 Grant, Thomas H.
 Grayson, Thomas
 Greiventhough, Geo. W.
 Grie, Wilfred B.
 Groves, Joseph L.
 Groves, Thomas
 Gurney, Walter R.
 Hadfield, Norman
 Hallworth, Walter
 Hampson, Frank
 Hancock, W. L.
 Harbach, Charles E.
 Hardy, Charles
 Hardy, Harold
 Harrison, John
 Harrison, Leonard
 Harrison, Sanson
 Harrison, William
 Hartley, Arnold
 Hartley, Horace
 Hawkins, William
 Hawley, John E.
 Cotterhill, Samuel
 Crabtree, Edwin
 Crosswell, Harry
 Crowther, Joseph H.
 Culley, Herbert
 Culley, Herbert
 Curtis, Roland W.
 Daley, William
 Davenport, Charles
 Davenport, Thomas
 Davies, Albert
 Davies, Arnold
 Davies, George
 Davies, George L.
 Davies, Phillip L.
 Davies, Samuel
 Davison, Harold
 Dawson, Tom B.
 Day, Fred
 Dean, Arthur
 Deane, Frederick J.
 Denmerley, Alfred
 Dickinson, William E.
 Diggle, Jack
 Douglas, Fred
 Douglas, John W.
 Downs, Albert E.
 Downs, James
 Downs, John W.
 Downs, William T.
 Drinkwater, D.
 Dudley, Herbert
 Duneau, Harry
 Dunkley, Tom
 Dyson, Rupert
 Dyson, William
 Eades, William
 Earnshaw, James
 Earnshaw, Joseph H.
 Eastwood, Alfred
 Eaton, Arnold
 Eaton, John
 Eaton, Percy
 Eaton, Wilfred
 Elliot, Ernest H.
 Elliot, Frank
 Ellor, John

The Names of the Fallen ☘

Heginbottom, John H.
 Higinbottom, Amos B.
 Higgins, Frank
 Hill, Enoch
 Hill, Joseph
 Hirst, Tom
 Holden, Herbert
 Hopwood, James
 Housfall, James
 Hough, Joseph
 Howard, Harry
 Howard, Harry
 Howard, Raymond
 Hudson, Albert
 Hughes, Thomas G.
 Hulme, John
 Hulme, Samuel
 Hurley, Vincent
 Hurst, Charles
 Ingham, Alfred
 Inman, Wilfred
 Jackson, Robert W.
 Jackson, Walter
 Jackson, W.
 Johnson, Thomas
 Jones, George
 Jones, Henry
 Kavanagh, Daniel
 Kelly, Edward
 Kemp, Edward
 Keyworth, Fredk. B.
 Keyworth, William
 Killday, Harry
 Knowles, Abel
 Knowles, Harry
 Knowles, James
 Knowles, William
 Langan, Anthony
 Leaver, Samuel
 Lomas, Albert
 Longden, Alfred B.
 Lowe, Fred
 Lowerson, Harry B.
 McDonald, Louis
 McDougal, Harry
 Madew, A.
 Magson, John
 Magson, Willie
 Malhalien, Leo S.
 Malpas, Ellis
 Manwaring, James
 Manwaring, Jas. (Jnr.)
 Margerison, Edward
 Marlow, Charles E.
 Marsh, Isaac
 Martin, Samuel
 Mason, Herbert
 Maude, James
 May, William
 Middlemiss, George
 Middleton, Joseph
 Moore, Percy
 Moores, John S.
 Moores, Wilfred S.
 Moorwood, Ed. H.
 Morrell, Ely
 Morrell, William A.
 Moss, Leonard G.
 Mount, James W.
 Myatt, Samuel Y.
 Nadin, Joseph
 Neal, Harold
 Newham, James
 Newham, Thomas
 Nixon, Frank
 Oakley, Eli
 Ogden, Joseph
 Oldfield, Allan
 Oldham, Herbert
 Oldham, Tom C.
 Owen, Herbert
 Parkes, Daniel
 Parkes, Samuel
 Pearson, Fred
 Pennington, William
 Platt, Jess
 Platt, James
 Prendergast, Joseph
 Preston, Philip
 Procter, Herbert W.
 Radford, John
 Rayner, Percy
 Redfern, Benjamin
 Redfern, Edwin
 Redfern, William
 Renshaw, Alec
 Renshaw, James H.
 Richards, Frank
 Thickett, Frank
 Threadgold, Harry
 Tomkinson, Charles
 Tonkin, John I.
 Turner, Samuel
 Vaughan, Charles J.
 Vickers, Thomas
 Wagstaff, George
 Wagstaff, Samuel
 Walker, Lewis
 Walker, William
 Ward, William
 Ward, William
 Warhurst, Samuel
 Watson, Percy
 Webb, Joseph H.
 Wells, Fred
 Weston, Charles
 Whitehead, Harry
 Whitehead, Herbert
 Whyatt, Joseph
 Wild, John T.
 Wilde, Handel
 Wilde, John
 Wilde, Joseph
 Wilkin, Norman
 Sleight, Frank
 Smith, James
 Smith, John
 Smith, Leonard
 Smith, Whitham
 Stantthorpe, Fred
 Stansfield, John
 Stenton, Tom
 Stevens, Harry
 Stopford, A.
 Stopford, G.
 Stott, James
 Swarbrick, Joseph
 Swindells, Thomas
 Swindells, Frank
 Taylor, Fred
 Taylor, Harry
 Taylor, James
 Taylor, Thomas
 Taylor, William
 Thatcher, James
 Thewils, Frank
 Thickett, Frank
 Threadgold, Harry
 Tomkinson, Charles
 Tonkin, John I.
 Turner, Samuel
 Vaughan, Charles J.
 Vickers, Thomas
 Wagstaff, George
 Wagstaff, Samuel
 Walker, Lewis
 Walker, William
 Ward, William
 Ward, William
 Warhurst, Samuel
 Watson, Percy
 Webb, Joseph H.
 Wells, Fred
 Weston, Charles
 Whitehead, Harry
 Whitehead, Herbert
 Whyatt, Joseph
 Wild, John T.
 Wilde, Handel
 Wilde, John
 Wilde, Joseph
 Wilkin, Norman
 Sleight, Frank
 Smith, James
 Smith, John
 Smith, Leonard
 Smith, Whitham
 Stantthorpe, Fred
 Stansfield, John
 Stenton, Tom
 Stevens, Harry
 Stopford, A.
 Stopford, G.
 Stott, James
 Swarbrick, Joseph
 Swindells, Thomas
 Swindells, Frank

The Millennium Sundial.

This modern feature was introduced to the park by the Council in the year 2000 to celebrate the Millennium. It stands near to the Victoria Street entrance to the park in front of the War Memorial.



Floral Coat of Arms

Is an inclined flower bed showing the Denton Coat of Arms in a display of appropriately coloured carpet bedding. It stands in front of the flagstaff proudly displaying the Green Flag.



The Mural


Was commissioned by the Denton Town Twinning Association with the co-operation of Denton & Audenshaw District Assembly. The mural, which was conceived by David Vaughan serves to commemorate both the second millennium and the continuing friendship between the people of Denton and Montigny le Brettoneux.



Memories of Victoria (Denton Park)

Bomb in Victoria Park

On Christmas Eve 1940, a 2 ton bomb fell near Hyde Hall Farm but did not explode. It was not uncovered and was later defused by the Bomb Disposal Squad in May 1942. A police sergeant named Vardy picked up a piece of metal from the crater and assumed that the bomb had already exploded. However, he later watched a training film and recognised the piece of metal he found which was identified as a "Kauf" ring (a device for retarding the bomb's progress into the ground). The Bomb Disposal experts found the bomb to be 20 ft down and safely defused it.



The two pictures show the German bomb at the time of its removal from Hyde Hall Farm. In the picture on the right, the gentleman shown is a Mr Cooper. Later, the defused bomb was displayed at the Bandstand in Victoria Park for one month to raise money for the National Air Raid Distress Fund. Its fins had been restored by the Progressive Engineering Company Ltd (later to become Sturtevant Engineering Co Ltd) in Acre Street.



Dancing in the park

Once a year all the schools took part in the dancing in Denton Park for what was known as Baby Week. A variety of dances were performed including Morris dancing. This was organised by the Denton Welfare Committee for mothers and babies who were very pleased to take part.



Baby Week 1928 as described by Ellen Hanson.

Here Ellen, aged about seven, is sitting in the front row, first right. The teacher is Miss Forth. This was the class from St Anne's School prepared for dancing in Denton Park. I remember that the girls of St Anne's School were asked to wear white dresses. Six or eight of us, girls only, walked in crocodile from St Anne's with teachers. Miss Simister and Miss Olive Forth (later Mrs Downs). – **Clare Knott (nee Bagnall)**

The area in the park where the dancing took place is shown in the photograph below. The picture was taken from a point to the left of where the swimming baths now stand. The baths were opened in 1975 by the Olympic swimmer Anita Lonsborough MBE. In the distance can be seen the War Memorial, to the right of which is the 'kiddies' playground' and roundabout, roughly where the swimming pool car park is now situated. The young lady in the centre of the photograph is Miss Susan Hallsworth.



In the past, there was little to do on Sundays. Shops and cinemas were closed and so most people went for a walk, often to the park dressed in their Sunday best clothes. We listened to the band and girls and boys assembled in separate groups. We threw money into a sheet for the band. You could pay to sit on wooden slatted chairs which when folded were kept underneath the bandstand. You could meet acquaintances and chat – girls often met their future husbands there – **Marion Redfern**

My father, George Matley, was born in 1892 in Taylor Street, Denton and emigrated to the United States in 1913. In July 1947 my father, mother Ellen and I sailed on the Queen Elizabeth for a reunion of our UK families after the war. When I arrived at my Aunt Sally's home in Denton, there was a letter waiting from Reginald Millington from

Northwich (whom I had met at a British War Veterans' picnic in the United States). We had corresponded and resumed our friendship. In August 1947, Reg visited Denton and we went for a walk in Victoria Park – which didn't close until dark.

We sat on a form and talked for a long time and it was about 10 p.m. when he asked me to marry him. We had talked so long that he had missed the last bus home and Cousin Mary found him lodgings for the night. Our parents met for dinner that week. My family and I returned to the US in October and Reg sailed on the Queen Mary in January.



The photograph above shows Reg and I on our wedding day on 17th April 1948 in America. Reg had served on HMS Bootle, a minesweeper, on D-Day and it was our purpose to visit our family in Denton for the 1994 D-Day anniversary. We made a point of visiting Denton Park and sitting on a form to reminisce. We were married for 48 years (Reg passed away in 1996). We had four children, eleven grandchildren and ten great grand children – to date 2007 – and it all began in Denton Park.

Elizabeth Matley Millington, Southampton, New Jersey, USA.

3. The Management of Victoria Park

General Aims of the Parks Improvements

The following is a list of aims that apply to the conservation of the park as a whole:

- To protect, restore and re-create the principal design intentions of the 19th and early 20th century park landscape, particularly with reference to the display beds, sporting facilities, path network, tree and shrub planting and the bandstand as a focal point.
- To protect and conserve historic features of importance.
- To outline initiatives for planting or the restoration of features to restore the historic character.
- To improve and diversify opportunities for recreation for the local and wider community within the context of the history of the park.
- To stimulate and encourage participation and involvement in activity in the park as well as the parks development, management and maintenance.
- To encourage greater awareness of the historical significance of the park.
- To ensure that proposals reflect the needs and wishes of the community and that they will be sustained in the long term.
- To improve general security with in the park.
- Research and gain external funding to help implement all of the above due to sources of internal funding being limited.

Approach to Restoration and Conservation

Historical research and analysis have been carried out to gain an appreciation of the historical development and importance of Victoria Park through working in partnership with Denton Local History Society. In light of limited funds this has to concentrate on the restoration of historic elements with the greatest historical value before the possibility of replacing lost features can be considered.

Principal Heritage Features

The continuing restoration of the bandstand and war memorial, which are the principal focal points of the park which reinforce the structure of the original layout of footpaths with in the park, as well as the maintenance of the new features including the staff and Ladies bowling cabins.

- **Edwardian Grade II Listed Bandstand**

Although usually regularly maintained through the parks and land management budget, has recently received a substantial renovation, after receiving a substantial grant from the Heritage Lottery Fund. Denton & Audenshaw District Assembly received specialist advice from Tameside MBC Conservation Officer and Building Surveyor to restore the bandstand to its former glory, including the original colours, to conserve the features historic character by means of the correct conservation techniques. (Please see appendix 7)

- **The War Memorials**

In Tameside including Victoria Parks are all maintained from a corporate dedicated budget on an annual basis, the last survey was carried out in August 2007 by Peter Stafford Tameside Councils Building Surveyor. With works carried out by James Knott & Sons of Ashton-Under-Lyne in preparation for Armistice Day. The works carried out on the Victoria Park War Memorial included –

1. Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.
2. Replace any missing/ damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags.
3. Re-paint lettering.

All conservation works on the memorial are carried out with the utmost care and in accordance with the appropriate conservation methods of listed monuments, to preserve the historical character of the memorial. If any major works were required specialist advice would be taken and a bid for Authorities Capital programme or a grant application would be put in place. (Please see appendix 8)

- **Bowling Greens**

Victoria Park has two bowling greens which have been situated in their original positions for over 80 years, both of which are open to public use through out the summer season. Three men's and one ladies bowling teams are based on the greens and play league and cup matches through out the summer. The greens are maintained through out the year through the Denton & Audenshaw District Assembly maintenance and operational budgets.

- **The Tennis Courts**

Were redeveloped in 2007 after receiving grants from various sources including Barclays 'Space for Sport', into a Multi Use Games Area allowing numerous activities to take place with in three separate areas, including tennis, football, basket ball and hockey. The new MUGA helps to promote various sports within Victoria Park and the local community restoring the former tennis courts and enhancing the appearance of the park. Although not a heritage feature at present the site has been used for tennis since 1920 so the redevelopment has been fitting to the parks heritage. (Please see appendix 9.)

- **The Millennium Sundial**

Was introduced by the Council in the year 2000 to celebrate the Millennium and compliments the historical character of the park through its design. Any maintenance on the feature would be funded through the Denton & Audenshaw District Assembly parks and land budget

- **Interpretation Boards**

Two A0 interpretation boards are placed within the park, displaying the history of the bandstand and the park. These were installed during the bandstand renovation and produced in conjunction with Denton Local History Society to promote and display the heritage of Victoria Park.

- **The Mural**

Was commissioned by the Denton Town Twinning Association with the co-operation of Denton & Audenshaw District Assembly. And was conceived by David Vaughan who was a local psychedelic artist that did work for the Beatles in the early 1960's, serves to commemorate both the second millennium and the continuing friendship between the people of Denton and Montigny le Brettoneux. Depicts scenes from famous paintings whilst combining historical landmarks from the local area and although not necessarily in keeping with the park does include links with the heritage of Denton. The mural receives regular maintenance to remove graffiti through the Denton & Audenshaw District Assembly parks and land budget.

- **Floral Coat of Arms**

Is an inclined flower bed featuring various carpet bed displays which have included the Denton Coat of Arms and the Scout Crest to celebrate a hundred years of scouting. The feature has been built to compliment the heritage of the park and can be changed annually to celebrate various historical events which have taken place.

- **The Formal Flower Gardens**

Have maintained a similar layout from when the park originally opened in 1913 and although the water feature is no longer present still compliments the historical nature of the park. The flower beds are changed on a seasonal basis containing various designs and planting, with flower stands introduced in 2007.

- **Horticultural Collections**

Although we are unaware of any significant collections within the park, any felled trees are given consideration regarding their replacements in the form of positioning and variety, eg the cherry tree bed near the centre of Victoria Park. The replacement of trees and shrubs would be provided from the Denton & Audenshaw District Assembly parks and land management budget.

- **Signage boards**

The numbers of signage boards are to be increased at the entrances, to provide information on events, park management details and a map of Victoria Park. The design of the boards are in keeping with the park, painted in the town's colours and include the Denton Coat of Arms.

- **Boundary Railings**

Are vertical bar railings, simple in style to marry with the pattern of railings more recently installed elsewhere in the park. Although clearly not the style of the original ornate railings, they are sympathetic to the original Edwardian character of the park, and harder wearing than the originals. We believe this solution provides the best value for money.

- **Surfacing**

The majority of Victoria Park requires resurfacing as the present surface is dilapidated and is in constant need of repair, causing the un-even appearance of the pathways throughout the park. This would need to be carried out using a visually pleasing surface that will complement the heritage of the park yet be durable and cost effective. For this to occur a source of external funding will be required.

- **Park Furniture**

Long term replacement of all the seating around the bandstand and formal gardens to be identical and of a heritage design, making a visual statement and giving uniformity and structure to the park. The introduction of the new seating will meet current standards of robustness, comfort, safety and style to respond to the historic character of the park; as well as new litter bins which will be robust and complimentary to the design of the seats. This will be funded by the Denton & Audenshaw District Assembly environmental rolling programme.

Although there has also been a number of features within the park which have been lost there is a present no plans to recreate them, as this would require considerable research and funding from external sources and at present the surfacing would need to take priority. Although changing circumstances in the future may allow this to be possible. (For more information please see Appendix 5).

4. Victoria Parks Community Use and Enjoyment

Victoria Park is popular with the local community, so much so that the Denton Elderly Persons Centre has changed its name to the Victoria Park Community Centre; and is enjoyed by a multitude of visitors. Denton and Audenshaw District Assembly are proud that Victoria Park provides a range of activities to entertain all members of society, from toddler through to OAP with facilities including the playground, MUGA and bowling greens.

The heritage features within the park are also used for regular events which take place within the park including the Summer Saturday Band Concerts of which there were eleven in 2007 within the bandstand, Denton Carnival and the Remembrance Day Service held at the War Memorial.

These events are publicised through posters which are displayed throughout Denton town centre and in the notice board within the park, what's on magazine, Wire magazine, the local news papers, the Tameside MBC website and Green Flag website as well as banners displayed around the town. Other information that also publicises the heritage of Victoria Park include a leaflet, two AO interpretation boards within the park as well as school packs with the history of Victoria Park for all the Primary Schools in Denton and Audenshaw.

Denton Local History Society

The photograph below shows members of the Denton Local History Society dressed in Victorian regalia. The picture was taken in the park in 2000 to celebrate the opening of the newly refurbished Council Offices.



Standing left to right: Angela Pitman, Jackie Pitman, Daniel Pitman, John Pitman, Frank Brown, Jean Marlor, Jill Cronin. Claire Knott, Gerry Cartwright, Lynne Rhodes, Frank Horsfield, Edith Freeman and Kate Kerry. Kneeling: Frank Rhodes and Paul Cronin.

The Denton Local History Society exists to research, record the history of Denton and publish people's memories. The Society collects, preserves and exhibits material from its archive which includes documents, maps, photographs and other artefacts.

Members meet monthly to hear a speaker and also once a month at workshops to research, prepare exhibitions and deal with enquiries. Members receive copies of their quarterly publication "The Dentonian".

Meetings are held on the second and fourth Tuesdays of the month. Workshops are at the Festival Hall, Peel Street, in Room 10. Meetings to hear speakers are held at the Victoria Park Community Association Centre.



Steve Marsland Head Teacher of Russell Scott Primary School proudly receiving their School Pack from Jean Marlor and Fred Heap of the Denton Local History Society, June 16th 2007 during the Bandstand Opening Celebratory Event.

Denton Local History Society worked in partnership with Denton & Audenshaw District Assembly to research the heritage of Victoria Park and the Bandstand. This was carried out to ensure that visitors were able to learn about the parks history through two A0 display boards with in the park as well as by creating school packs to be provided to all the primary school in Denton and Audenshaw. Much of the history with in this application was provided through the research of the group and has been of great assistance to ourselves in 'bringing to life' the historical value of Victoria Park.



Denton Carnival

The town Carnival has taken place intermittently over a considerable number of years. Usually held in September, the event centred round a procession of well decorated floats –carts, lorries and other conveyances – paraded along the town centre roads. Young and old dressed for the occasion and competed with each other for the best float. Sadly, the Carnival lost favour during the 1970s.

When the town twinning was organised in 1992 by Mr Fred Elms, a delegation of Denton dignitaries was invited to its French counterpart, Montigny in France and were extremely well received. A reciprocal visit to Denton by a French delegation took place in 1993 and, to celebrate the occasion, the Carnival was regenerated. Mr Elms successfully organised the event which relied heavily on the goodwill of local tradesmen. It continued for several years by which time Mr Elms, former Headmaster of Egerton Park School had retired. Mr Dennis Fogg then took over as Carnival Organiser.



Town twinning- Denton and Montigny Le Bretonneux, France



The photograph was taken during the Memorial Service which was conducted by the Rev J Tutton – to celebrate the twinning in 1993 of Denton and the French town of Montigny which is near Paris. Present were dignitaries from Denton including Mr Fred Elms, former Headmaster of Egerton Park School who negotiated the twinning. The Mayor of Montigny (Monsieur About) and his wife, together with the then Mayor of Tameside, Cllr Albert Hatton, can be seen at the front of the main group, ready to place wreaths at the Cenotaph, near to the flagpole, are the Town Crier and his lady.

Bandstand Opening Celebratory Event on the 16th of June 2007

The Bandstand underwent major refurbishment in spring 2007 after receiving external funding from numerous sources with the main contributor being The Heritage Lottery Fund, helping to preserve the bandstand for years to come. Various community groups supported the project including The Friends of Victoria Park, Denton Local History Society, Russell Scott Primary School, Denton Brass Band and the Local Scout Group to name a few. Denton Local History Society were also commissioned to look further into the Heritage of the park and the bandstand, producing school packs for all the primary schools in Denton & Audenshaw and two interpretation boards featuring the heritage of the park and bandstand placed within Victoria Park. The Bandstand Opening Celebratory Event, see picture above included a procession of Civic Dignitaries, Town Crier, Denton Local History Society in Edwardian costume escorted by the Denton Scout Group with the local members unveiling the interpretation boards and declaring the bandstand open. The bandstand, now painted in its original colours and once again boasting a Zink roof was the centre of entertainment including Denton Brass Band and Musical Youth who were very well received. Family entertainment was also featured during the celebration for the local community including fair ground rides, circus skill workshop, face painting, refreshments and the Countryside Service. (Please see appendix 7.)



Before Restoration



After Restoration



Bandstand Opening Celebratory Event

5. Conclusion

Victoria Park still contains many features and much of the original layout including the Grade II listed Edwardian Bandstand and War memorial which are still used on a regular basis. The Historical features with in the park act as the main focal points and are regularly maintained, using the appropriate conservation techniques to conserve the historical character and infrastructure of the park. Victoria Park is well used and highly valued by the community of Denton, with regular use of the facilities including the play ground, bowling greens and multi use games area as well as the summer events within the bandstand. Denton & Audenshaw District Assembly worked in partnership with Denton Local History Society to produce two A0 interpretation boards, which include information on the heritage of the park and bandstand. As well as school packs for all of the primary schools in Denton and Audenshaw.




Victoria Park 2006




Victoria Park 2007

Denton & Audenshaw District Assembly



is proud to present



Summer Saturday Brass Band Concerts

**Victoria Park, Denton
Band Stand 2 - 4 pm**

June 23rd - Tintwistle Band

June 30th - Mossley Hollins Band

July 7th - Stalybridge Old Band

July 14th - BelleVue Brass Band

July 21st - St John's Droylsden

July 28th - Carrbrook Brass Band

September 1st - Tintwistle Band

September 8th - Denton Brass Band

September 15th - St John's Droylsden


September 22nd - Adamson Military Band




 **Tameside**
Metropolitan Borough
"An excellent council"

61226

Denton & Audenshaw District Assembly



is proud to present



Bandstand Opening Celebratory Event

Saturday 16th June

**Victoria Park, Denton
Band Stand 12 - 4 pm**

Official Opening

Denton Brass Band

Musical Youth

**Fun & Frolics
for all the family**

 **Tameside**
Metropolitan Borough

'An excellent council'



61443




9th Floor
82 King Street
Manchester
M2 4WQ

Telephone
0161 831 0850
Facsimile
0161 831 0851

16 May 2006

Our Ref: YH-05-01730

Stuart Mollison
Denton & Audenshaw District Assembly
Tameside Metropolitan Borough Council
Town Hall
Market Street, Denton
Manchester
M34 2AP



Dear Stuart

Banding Together - The Victoria Park Bandstand Project - Your Heritage

Congratulations! Your application has been assessed, and I am pleased to inform you that we have decided to award you a grant of up to £47,800 (72% of the total eligible project cost of £66,201) towards the conservation of the grade II listed Victoria Park bandstand and enabling the wider community to learn more about the bandstand through interpretation panels and an education pack to be produced by the Local History Society.

The attached appendix sets out the main elements of the project to which HLF has agreed to contribute along with the anticipated partnership funding.

The following documents define the project for which the grant is offered:

1. This letter
2. Your application dated 13 March 2006
3. Documents submitted by you in support of your application

This award has been made in accordance with the signed Contract submitted with your application. The Contract is between Denton & Audenshaw District Assembly (Tameside MBC) and the Trustees of the National Heritage Memorial Fund. The Contract has now been signed on behalf of NHMF and I enclose a photocopy of the Contract along with the following Monitoring Documents:

- Monitoring Guidance document
- Grant Payment Request 1 form
- Grant Payment Request 2 form
- Grant Payment Request 3 form
- Volunteer Time Sheet
- How to Acknowledge Your Grant guidance
- Hitting the Headlines
- Example press release

Please read the Contract in conjunction with all of the Monitoring Documents which have the same legal status as the Contract.

Awarding funds from
The National Lottery



Head office: 7 Holbein Place London SW1W 8NR www.hlf.org.uk
Tel 020 7591 6000 Fax 020 7591 6001 Textphone 020 7591 6255
Administered by the Trustees of the National Heritage Memorial Fund

The Monitoring Documents enclosed provide more information about our procedures and will guide you through the monitoring process, explaining the information you may need to provide.

I look forward to receiving the Grant Payment Request 1 form **within 20 working days from the date of this letter**. However, if you have any difficulties in meeting this deadline, please let me know. **Please note that you must not commence project work until HLF has signed and returned the Grant Payment Request 1 form.**

It is important to publicise your award to local media so that lottery players know where their money has gone. However you must keep your award confidential until we have discussed and agreed your publicity plans. We will publish the fact that you have been awarded a grant on our website within 10 days of the grant being awarded. I can assist you with queries about publicity and the media and I have enclosed a template press release which you may find helpful to issue to media once your publicity plans have been agreed.

Please also contact me as soon as possible to agree the most appropriate location and nature of HLF acknowledgment for your project both during and after its completion. This includes making sure you include our logo on any information you produce about your project, for example, on public consultation or fundraising information or materials. You must also include our logo on all designs or plans you produce, on all specialist reports, or surveys and on all tender documents that are funded by our grant. Please refer to the enclosed How to Acknowledge Your Grant guidance which explains how to do this.

Please also liaise with me throughout your project to discuss any celebration or marking of a project achievement, such as the laying of a foundation stone or opening event, at which a representative from HLF can attend and speak on behalf of the lottery players who made the project possible.

I wish you every success with your project. Please contact me if you have any queries arising from this letter.

Yours sincerely



Nicola Marshall
Grants Officer
Direct Line: 0161 831 0871
Fax: 0161 831 0851
Email: NicolaM@hlf.org.uk

Enc

Appendix

TOTAL PROJECT COSTS	£ 66,201.00
CAPITAL COSTS	
Repair and Conservation Works	
Repair and conserve the bandstand	£ 54,320.00
TOTAL CAPITAL COSTS	£ 54,320.00
ACTIVITY COSTS	
Professional fees for consultancy and advice	
Denton Local History Society research and production of 100 education packs	£ 2,500.00
Non-cash contributions and volunteer labour related to activities	
1 Officer for 35 days @ £150 per day	£ 5,250.00
TOTAL ACTIVITY COSTS	£ 7,750.00
OTHER COSTS	
Contingency	£ 2,951.00
Inflation	£ 1,180.00
TOTAL OTHER COSTS	£ 4,131.00
PARTNERSHIP FUNDING	
Cash from your organisation	£ 2,151.00
Tameside MBC	£ 11,000.00
Non-cash contributions	£ 5,250.00
TOTAL PARTNERSHIP FUNDING	£ 18,401.00
HLF Grant Award	£ 47,800.00
HLF Grant %	72%

Planning and Building Control

Nigel C Allen BA MRTPI
Head of Planning

Council Offices, Wellington Road
 Ashton-under-Lyne, Tameside. OL6 6DL

FAX 0161-342 3111
 Minicom 0161-342 2283

www.tameside.gov.uk

Your Ref
 Our Ref ER/PHBF
 Doc Ref Offer letter - 30October2006
 Ask for Elisabeth Read
 Direct Line 0161 342 3118
 Date **30th October 2006**

Stuart Mollison
 Town Manager
 District Assemblies
 Denton Town Hall
 DENTON
 Tameside

Dear Stuart,

Tameside MBC'S Preservation of Historic Buildings Fund Grant

I am writing regarding the Council's **Preservation of Historic Buildings Fund** and grant assistance available to you to carry out repair works to the Victoria Park Bandstand, Denton.

1. Tameside Metropolitan Borough Council (TMBC) is willing to make you an offer of grant assistance from the Preservation of Historic Buildings Fund.
2. The total grant offer of up to **£11,000.00 (excluding VAT)** relates to the repair works to the approved repair works at Victoria Park Bandstand, Denton. The approved works are those agreed as part of your application for a grant under the Preservation of Historic Buildings Fund scheme.
3. The total grant of **£11,000.00** is contribution towards the tender submitted as part of your application, by **Dorothea Restoration**, for the total sum of **£54,320.00 (excluding VAT)**. The tender submitted by Dorothea Restoration was deemed to be the lowest following arithmetical and technical checks.
4. As you able to recover VAT, the grant allocation does not include the VAT element of the project costs.
5. The above offer is based on the following figures, which should be read in conjunction with the tender document submitted by Dorothea Restoration as part of the application.

Total cost of works (excl. VAT)	£54,320.00
Total cost of eligible works (excl. VAT)	£54,320.00



2000-2001
 Preventing Crime
 and Disorder



2001-2002
 Maintaining a
 Quality Environment



2001-2002
 Accessible
 Services



2002-2003
 Community
 Legal Services



2005-2006
 Getting Closer
 to Communities



INVESTOR IN PEOPLE

Grant Offer (excl. VAT)

£11,000.00

The grant offer of £11,000.00 (excl. VAT) is based on an agreed fixed contribution to the total cost of the eligible works.

6. The works now exceed the threshold of £10,000 in total and therefore by law and as a requirement of the PHBF we request the appointment of an agent to oversee the works.
- This will require approximately three site visits by the appointed agent, usually at the start, during the middle stages and on completion of the works to sign them off. The agent must be a chartered by either RICS or RIBA. This does not affect the grant amount available, however you may incur an additional fee by the agent for their services.
5. This grant offer is made on the understanding that the works **will be completed** as soon as possible. **You should notify Helen Charlesworth (Design & Regeneration Officer ex 2214) should works commence whilst I am on maternity leave. Please inform Helen of the start and end dates and length of the works once these are confirmed so that an Officer can arrange a minimum of three site visits during the works.**
6. The grant is subject to the attached terms and conditions and you should demonstrate your acceptance of the grant and the attached grant conditions by signing both copies of this letter and both copies of the grant conditions, retaining one copy of each for your own records and returning one copy of each within **one month** of the date of this letter to:


Helen Charlesworth
Design & Regeneration Officer
Planning & Building Control
Tameside MBC
Wellington Road
Ashton-Under-Lyne OL6 6DL

Yours sincerely,

Elisabeth Read
Conservation Officer

Enc: **Standard Grant Conditions x2**
Grant Offer Specification-Guidance

If you have any queries regarding this please do not hesitate to contact Helen on extension 2214.

Signature of Applicant


Date of Acceptance
5/11/06



Architectural & Engineering Metalwork Conservation

Please reply to:

Northern Works

9th March 2006

Mr Peter Stafford
Tameside Borough Council
Wellington St
Ashton under Lyne
OL6 6DL

David Hodgson
MOB 07739 522074

Dear Peter

September?

Victoria Park, Denton – Bandstand

Thank you for your e-mail of the 7th March 2006. We are pleased to forward revised costings as per your listing, as below.

We would point out that we have been notified of above-inflation price rises in numerous materials over the last few months, including zinc, wrought iron, steel, lead and paint. In addition, we have been warned to expect further price rises in the near to middle future.

	£
Page 1	25,260.00
Page 2	nil
Page 3	20,390.00
Page 4 (item K: 1)	3,920.00
Page 4 (item K: 2)	2,420.00
Page 5 (item M)	750.00
Page 5 (item N)	1,580.00
Total	£54,320.00
(All ex VAT).	

Our pricing is based upon an order or letter of instruction being received within two weeks of today's date, for a start on site at the beginning of May.

I trust that you will find the above to be in order and look forward to hearing from you again shortly.

Yours sincerely

David Hodgson
For Dorothea Restorations Ltd

New Road, Ashton-under-Lyne, Greater Manchester, M34 2JF
Tel: 01 663 733544 Fax: 0 663 734521 Email: north@dorothearestorations.com

Southern Works:
Riverside Business Park, St Annes Road, St Annes Park, Bristol BS4 4ED
Tel: 0117 971 5337 Fax: 0117 977 1677 Email: south@dorothearestorations.com



www.dorothearestorations.com



Architectural & Engineering Metalwork Conservation

Please reply to:

Northern Works

6th Oct. 2005

Mr Peter Stafford
Property Services
Tameside Council
Wellington
Ashton under Lyne
OL6 8DL

Dear Peter

Victoria Park, Denton – Bandstand

We are pleased to forward the priced breakdown of our tender of the 22nd September. By way of clarification, we forward the following assumptions and notes:

We have allowed for 'Heras' type temporary fencing as per the specification but query whether a more substantial vandal-resisting system might be required.

With regard to painting, we have allowed for cutting back to sound surfaces to allow for recoating as required. This includes for the blast-cleaning of dismantled and rusted ornamental components. We have not allowed for the wholesale blast-cleaning of all metal surfaces.

We understand that local supplies of electricity and water would be available in connection with the works, at no charge. We assume that access to the site would be freely available and at all reasonable times, along with parking for service vehicles.

We confirm that we are presently in a position to commence work in approximately 3 weeks time.

Trusting that you will find our pricing to be acceptable, we look forward to hearing from you further.

Yours sincerely

David Hodgson
For Dorothea Restorations Ltd.

Northern Works:

New Road, Whaley Bridge, High Peak, Derbyshire SK23 7JG

Tel: 01663 733 544 Fax: 01663 734521 Email: north@dorothearestorations.com

Southern Works:

Riverside Business Park, St Annas Road, St Annas Park, Bristol BS4 4ED

Tel: 0117 971 5337 Fax: 0117 977 1677 Email: south@dorothearestorations.com



www.dorothearestorations.com

Job: Refurbishment to the bandstand, Victoria Park, Denton					
TAMESIDE METROPOLITAN BOROUGH ECONOMY AND ENVIRONMENT PROPERTY SERVICES Architectural Services Unit				£	P
A	SPECIFICATION AND SCHEDULE OF WORKS Include for removal from site all debris waste and surplus materials. Allow for reinstatement/ replacement of any damaged finishes, which may occur as a consequence of the building works. Allow for full contract clean on completion of the contract. All dimensions, details, to be agreed with the contract administrator prior to works being undertaken. Scope of work			750	=
B					
C	To be read in conjunction with condition survey dated April 2005: A totally minimalist approach to repairs to be undertaken, in conjunction with traditional methods of construction with original specified materials where appropriate. The ethos of The Society For the Protection of Ancient Buildings and English Heritage to be adopted when determining repair/replacement techniques. Also consideration should be given to PPG15, particularly Annex C. The work consists of the total refurbishment to a Victorian bandstand, which is a Grade II listed building situated within the Victoria Park Denton. Roof: 2 Carefully remove weather vane and attached wrought iron work, refer to survey and recreate replacement details ready for re-fixing. Re-fix Remove felt covering and repair decking/support metal work as required. Provisional sum. Replace covering with zinc sheet as follows: Extract taken from the British Standards Institute Code Of Practice CP 143-5:1964 – Sheet roof and wall coverings- Part 5:Zinc Section 1. General 101 Scope This Part of the Code deals with zinc roof covering and gives recommendations based on accepted good practice in the United Kingdom for laying zinc roofs on the Roll Cap System. In this system the sheets are fully supported and have their sides turned up against shaped wood rolls spaced to suit the width of the sheets. The rolls are covered with an independent capping which completes the joint. Joints between the ends of sheets are made either by means of drips or welts depending on the pitch, see Figure 1 and Figure 2. Recommendations are given for the whole of the roof covering above the upper surface of the constructional base for both flat and pitched roofs. Flashings and gutters are also dealt with in so far as they are integral parts of the roof covering.	Item		2,50	=
			5,000.00	5,000	=
		46m2	+	15,213	=
Total Carried to Collection				23,473	=

Job Nr: 3004-043

1

P: 2/9

10:0161613423555

7-OCT-2005 11:35 FROM:DOROTHEA RESTORATION 01663 734521

Job: Refurbishment to the bandstand, Victoria Park, Denton						£	p
<p>102 Definitions For the purposes of this Code, the definitions given in BS 2717z) apply.</p> <p>Section 2. Materials, appliances and components</p> <p>201 Zinc sheet Zinc sheet should comply with Part 1 of BS 849s). The United Kingdom stock or standard sizes of sheets for roofing work are 3 ft wide by 7 or 8 ft long; purpose made sheets of other dimensions can be obtained. A table of weights, gauges and thickness in inches of zinc sheets is given in Clause 602 and is based on the weight of one square foot of inch thick material. It should be noted that the English Zinc Gauge, as distinct from the Standard Wire Gauge, rises in number with thickness. On permanent buildings, roof coverings and ancillary parts should not be thinner than No. 14 ZG (approximately 21 SWG). No exterior zinc work should be thinner than No. 12 ZG (approximately 23 SWG).</p> <p>202 Nails Nails should be of steel either heavily galvanized or otherwise provided with a zinc coating of equivalent thickness. They should comply with BS 12024). Galvanized clout nails not less than 1 in long should be used for fixing the zinc.</p> <p>203 Screws Screws should be of steel coated similarly to steel nails and should comply with BS 1210s). 2) BS 2717, "Glossary of terms applicable to roof coverings". 3) BS 849, "Plain sheet zinc roofing". 4) BS 1202, "Wire nails and cut nails for building purposes". 5) BS 1210, "Wood screws". CP 143-5:1964 2 * BSI 02-2000</p> <p>204 Underlay Suitable materials for underlays are open-textured impregnated felts such as those defined under Type 4A ii), BS 7476). Materials other than those defined above may be used provided that they are porous and are not liable to become "tacky" in service.</p> <p>When the surfaces to be soldered cannot be pre-cleaned, hydrochloric acid (commonly known as "Spirits of salts") may be used. Flux residues should be washed off joints immediately on completion.</p> <p>206 Roll capping Square section roll capping (see Figure 4) is machine made from zinc sheet and shall be of the same thickness as the roof covering. It is usually supplied in lengths of 8 ft, but should not be fixed in lengths of more than 4 ft.</p>							
Total Carried to Collection							

Job Nr: 3004-043

Job: Refurbishment to the bandstand, Victoria Park, Denton		£	p
	<p>205 Solder and soldering fluxes Solder for use on zinc should be antimony free, and either 50/50 or 60/40 tin/lead, corresponding to grades F and K in BS 2197. The flux generally used is zinc chloride solution (commonly known as "Killed spirits") either alone or with the addition of ammonium chloride. There are also proprietary non-acid liquid fluxes which are equally suitable. When the surfaces to be soldered cannot be pre-cleaned, hydrochloric acid (commonly known as "Spirits of salts") may be used. Flux residues should be washed off joints immediately on completion.</p> <p>206 Roll capping Square section roll capping (see Figure 4) is machine made from zinc sheet and shall be of the same thickness as the roof covering. It is usually supplied in lengths of 8 ft, but should not be fixed in lengths of more than 4 ft.</p>		
D	<p>Soffit: Carefully remove the existing plywood soffit and take to tip. Inspect metal support structure and repair as required, refer to report for the anticipated extent of repairs required. Provide timber supports for fixing soffit to. Re-paint metal work with a sympathetic coating. Fit replacement soffit covering, material to be used, pitch pine "V" grooved boarding 4 in wide fixed by secret lost head nails. Timber to be filled and rubbed down as required then finished with three coats of clear silk varnish, design to be as survey. Allow for installing trap door access into roof space</p>	45m2 Item	6,230 =
E	<p>Rainwater goods: Re-seal all joints to the cast iron gutter, check all fixings for integrity, re-fix as required. Clean out both discharge tubes through the cast iron columns; ensure that both tubes are free from any blockage.</p>	Item	900 =
F	<p>Metal work: Repair all damaged wrought iron work using traditional methods of construction, and to the original design, including forge welded joints, riveted joints, etc. Florets to be recreated using the Repousee method. Puddled iron to be used. Under no circumstances shall mild steel be used, and no electric welded joints! Replace any missing elements of ironwork as above; prime any bare metal ready for painting. Replace the recent mild steel gates and balustrade to match the original design/specification, fix to steps using leaded sockets. Manufacture notice board brackets to fit the positions on 4 of the cast iron columns (design to be agreed) Wrought iron works to be completely restored back to the original design.</p>	Item	11,810 =
Total Carried to Collection			18,940 =

Job Nr: 3004-043

3

P:479

TD:0161613423555

7-OCT-2005 11:35 FROM:DOROTHEA RESTORATION 01663 734521

Job: Refurbishment to the bandstand, Victoria Park, Denton							
						E	P
G	<p>Plinth Base:</p> <p>Concrete base to be broken up and taken to tip, substrate to be excavated and removed completely, investigations showed that the base was 50mm screed on 100mm concrete slab on 950mm of fill. All these materials require removing to tip. Depending upon what is found when the excavation is complete please price for two options.</p> <p>Option 1: Lay 150mm reinforced concrete slab on 1200-gauge visqueen damp proof membrane on sand blinding on M.O.T. fill, compacted in 300mm bands. Slab to have a smooth floated finish.</p>	Item				7,080 =	
	<p>Option 2: Install a suspended timber floor, constructed in pitch pine and including a fire retardant coating and trap door to allow for storage in the void below. Provide steps to access the void. Provide 100mm over site concrete trowelled to a smooth finish to void base, concrete to be laid on 1200 gauge visqueen on sand blinding on 150mm compacted M.O.T fill</p>	Item					
H	<p>Brickwork:</p> <p>Clean and re-point as per survey details.</p>	15m2				3,000 =	
I	<p>Copingstones/steps:</p> <p>Repair/replace as per survey details.</p>	Item				6,450 =	
J	<p>Drainage:</p> <p>Test drainage system and repair any damaged below ground elements -- Allow provisional sum.</p>		2,000.00			2,000 =	
	<p>Repair/replace gullies and grates as per survey</p>	Item				750 =	
K	<p>Paintwork:</p> <p>The paintwork is to be prepared as per the survey, but the exercise requires to be conducted in two phases, with the first phase this year, leaving the metalwork ready to receive the finish coats prior to the unveiling of the refurbished project in the summer of 2006. These costs will be paid accordingly</p> <p>Therefore two sums need to be identified, the first sum to prepare the metal work and prime.</p>	Item				3,750 =	
	<p>The second sum to provide the subsequent topcoats.</p>	Item				2,300 =	
Total Carried to Collection						25,310 =	

Job Nr: 3004-043

4

P: 5/9

T0: 01613423555

7-OCT-2005 11:36 FROM: DOROTHEA RESTORATION 01663 734521

Job: Refurbishment to the bandstand, Victoria Park, Denton							
					£	P	
L	<p>Parterre:</p> <p>Replace soil to bring levels up to the original, re-align p/n kerbs as required. Lay good quality turf as per survey. Leave bed ready for replanting.</p>	Item			2,050	=	
M	<p>Fencing:</p> <p>Provide 'Heras' type fencing or similar for the complete contract period to completely enclose the bandstand and allow access for work to progress, provide any sheeting required to allow progress of works through any inclement weather.</p>	Item			700	=	
N	<p>Scaffolding:</p> <p>Provide suitable scaffolding for the contract period to allow works to progress, including support for protective sheeting.</p>	Item			1,500	=	
O	<p>Electrical:</p> <p>During the investigations, an electrical supply was detected in the substrate to the plinth base, as reported in the survey, price to identify this supply, connect into this supply, run the supply through the column central core void identified in the survey as having housed the former electrical supply, and terminate the supply in the roof space leaving the supply ready for future use. We anticipate that outlets be included for lighting and power. Provisional sum.</p>		1,000.00		1,000	=	
Total Carried to Collection					5,250	=	

Job Nr: 3004-043

5

P: 6/9

TO: 0161613423555

7-OCT-2005 11:36 FROM: DOROTHEA RESTORATION 01663 734521

Job: Refurbishment to the bandstand, Victoria Park, Denton				
			£	p
Prelims & General Conditions				
Provisional sums: Included in schedule.				
Cost of prelims & contractors items carried forward from page p11.				
Contingencies: To be expended as instructed by CA.				
			2,000	00
Total Carried to Collection			2,000	=

Job Nr: 3004-043

6

P: 7/9

TO: 01613423555

7-OCT-2005 11:36 FROM: DOROTHEA RESTORATION 01663 734521

Job: Refurbishment to the bandstand, Victoria Park, Denton						
					£	p
COLLECTION						
Total From Page		1			23,473	=
Total From Page		2				
Total From Page		3			18,940	=
Total From Page		4			25,310	=
Total From Page		5			5,250	=
Total From Page		6			2,000	=
Total From Page		7				
Total quotation amount					74,973	=

Job Nr: 3004-043

8

P: 9/9

TQ: 0161613423555

7-OCT-2005 11:37 FROM: DOROTHEA RESTORATION 01663 734521


Ashton Memorials: Condition survey

Memorial 8. Victoria Park Memorial, situated in Victoria Park, Denton. Not listed

General view



Lettering to the memorial



General condition: Reasonable/good.

Requirements:

Lightly clean the monument and steps using a neutral PH cleaner, applied with a soft brush to remove lichens and graffiti.

Remove all weed growth from the monument and surrounding viewing areas.

Replace any missing/damaged pointing to the monument and base with a mix of 1:2:9 – Portland cement: Lime: Sharp washed sand, pointing to be slightly recessed from the stone.

Note: Lettering is becoming difficult to read, recommend to re-paint as soon as possible



Neighbourhood & Community Services

District Assemblies

Council Offices, Wellington Road,
Ashton-under-Lyne, Tameside. OL6 6DL

Call Centre 0161-342 8355
FAX 0161-342 4149
Minicom 0161-342 2283
Website: www.tameside.gov.uk

Your Ref
Our Ref PN/AU
Ask for Peter Noden
Direct Line 0161 342 3328
Email peter.noden@tameside.gov.uk
Date 3rd September 2007

Mr N Milhench
James Knott & Sons
Mossley Road
Ashton under Lyne
OL6 9RH

Dear Mr Milhench

Re : Work to War Memorials 2007

Could you please provide a quotation for the work on Tameside's memorials as listed below:-

1. Ashton War Memorial

Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.

Replace any missing/damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags

Replace missing corner stone to match existing material

Reset the dislodged stone steps positioned at the base of the plinth

2. Waterloo War Memorial, Ashton under Lyne

Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.

Replace any missing/damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags

3. Hurst Cemetery, Ashton under Lyne

Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.



Replace any missing/damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags

4. Hurst Cross, Ashton under Lyne

Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.

Replace any missing/damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags

5. Park Bridge, Ashton under Lyne

Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.

Replace any missing/damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags

6. Audenshaw Cemetery

Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.

Replace any missing/damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags

7. Broadbottom Memorial

Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.

Replace any missing/damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags

8. Victoria Park, Denton

Lightly clean the monument and steps using a neutral pH cleaner, applied with a soft brush to remove lichens and graffiti.

Replace any missing/damaged pointing to the monument and flagged viewing area with a mix of 1:2:9 Portland Cement: Lime: Sharp Washed Sand, pointing to be slightly recessed from the stone flags

Re-paint lettering



Logged in as Peter Noden



VIEW ORDER

<p>SUPPLIER</p> <p>Contact: Business Name: James Knott & Sons Monmtl Name: Stonemason Property No: Property Name: Mossley Road Street Name: Corner of Area: Infirmiry Road Town: Ashton Under Lyne County: Lancashire Post Code: OL6 9RJ</p>	<p>ENQUIRIES TO : Peter Noden</p> <p>DELIVER TO</p> <p>Contact: Peter Noden Business Name: Property No: RM3.65 Property Name: Tameside MBC - District Assemblies Street Name: Wellington Road Area: Town: Ashton under Lyne County: Tameside Post Code: OL6 6DL</p>	<p>TELEPHONE : 0161 342 2328</p> <p>INVOICE TO</p> <p>Contact: Creditors - eproc Business Name: Property No: RM 4.8 Property Name: Tameside MBC Council Offices Street Name: Wellington Road Area: Town: Ashton under Lyne County: Tameside Post Code: OL6 6DL</p>
---	---	--

ORDER NUMBER: 082106553

ORDER STATUS: Closed (Delivery Complete)

ORIGINAL INVOICE TO BE RETAINED: Check this box if the order is Capital or Grant funded and the original invoice needs to be retained by the department for proof of spend.

Ordered for ServiceUnit: Neighbourhood & Community Services (DA'S) and Workgroup: Landscape Management

You may enter update comments, resend and cancel this order or its lines (if available). To update the comments click the **UPDATE ORDER** button.
 To resend this order by clicking on the **RE-SEND ORDER** button.
 To cancel the whole order, click the **CANCEL ORDER** button.
 To cancel a line, check the cancel checkbox next to the line and click the **UPDATE** button.
 NOTE: You may not be able to cancel a line as it may already have deliveries against it. If so it will be marked as **Can't Cancel**.



Line	Contract Ref	Product	Agresso Code	Sold In	Price *	Qty	Value	In Dispute?	Cancel
1		Please carry out cleaning, repair and re-lettering work to war memorials as quoted in your letter dated 25/09/07	R2007 PC801100		1 8145.00 Q	1	8145.00	<input type="checkbox"/>	Can't Cancel
Total Order: 8145.00									

Comments

Order Comments (max 250 characters)

Internal Comments (250 characters remaining)

Victoria Park Ball Court file



Mr S Mollison
Town Manager for Denton, Audenshaw and Dukinfield
Denton Town Hall
Market Street
Denton
Tameside

20 July 2007

Dear Stuart,

VICTORIA PARK BALL COURT.

Income

Barclays Spaces for Sport	£50000.00
Tameside Sports Trust	£15000.00
TMBC various*	£15000.00
Tameside Trust	£15000.00
Groundwork Tameside	£00600.00 (to cover CDM Coordinator)
TMBC**	<u>£01870.00</u>
Total***	<u>£97470.00</u>

Estimated Total Project costs:

Main works	£85564.08 (see attached spread sheet)
Aqua speed	£00426.00
Planning application	£00360.00
CDM Coordinator	£00600.00 (estimate)
GWT Fees****	<u>£14090.00</u>
Total	<u>£101040.08</u>

*As your letter dated 16th June 06

**As email from Nick Sayers dated 17 April 07

***Assumes VAT is excluded or recoverable

****Covers consultation, bid writing, design and contract management.

This gives an estimated short fall of £3570.08 and assumes all monies committed to the scheme are now secured. I trust this is clear, if you have any queries please contact me to discuss

Yours sincerely,

NICK LINDER
LANDSCAPE ARCHITECT

Groundwork Tameside
Birchcroft
Crowthorne Road
Ashton-under-Lyne
Tameside OL7 0DH
Telephone 0161 3426767
Facsimile 0161 3426768

CHANGING PLACES
CHANGING LIVES



goodcorporation



Victoria Park BS4S MUGA

SCHEDULE OF WORKS

Contractor name: **Urban Progress**

Contract Sum
25-Apr-07

Predicted Contract Value
10-Jul-07

Valuation 01
29-Jun-07

Item Section / Clause	Description	Qty	Unit	Rate	Total	Qty	Unit	Rate	Total	Qty	Unit	Rate	Total
PRELIMINARIES													
A11	Tender and Contract Documents												
1	Method Statement		Item				Item				Item		
2	Provide written maintenance schedule for tree and woodland planting.		Item				Item				Item		
Employer requirements: Management of the Works													
3	210; 250. Programme of the works including revisions through the life of the contract as requested by the CA.		Item		£25.00		Item		£25.00		Item		£25.00
4	120; A20/6.2 & 6.3A. Cost for providing adequate insurance.		Item				Item				Item		
Employer requirements: Quality Standards/Control													
5	320 Setting out for external works operations.		Item				Item				Item		
Security/Safety/Protection													
6	140 Price here for acting as Principle Contractor and compliance with Construction (Design and Management) Regulations 2004.		Item		£250.00		Item		£250.00		Item		£250.00
7	150 At the Contractors discretion adequately safeguard the site, the works, products, materials, plant and any existing buildings or site features affected by the Works. Proposed internal boundary fence within park is 112m long.		Item		£750.00		Item		£750.00		Item		£750.00
8	560 Protect bitmac surfaces and grassed areas from damage by plant and materials caused in undertaking the Works.		Item		£1,100.00		Item		£1,100.00		Item		£0.00
Facilities / Temporary Works / Services													
9	230 Site accommodation, toilets secure compound; as necessary and to comply with current HSE guidelines.		Item		£1,100.00		Item		£1,100.00		Item		£550.00
10	330 Protection of the existing trees on the site to BS5837, as shown on Dwg.10607/2249/01.	44.0	Lm	£7.00	£308.00	44.0	Lm	£7.00	£308.00	44.0	Lm	£7.00	£308.00
11	430 Supply of water for the Works.		Item				Item				Item		
GROUNDWORK													
D20 GROUNDWORK													

GROUNDWORK TAKESIDE

20/07/2007

Page 1 of 6

Victoria Park BS4S MUGA

Contractor name: **Urban Progress**

SCHEDULE OF WORKS

Item	Section / Clause	Description	25-Apr-07			10-Jul-07			29-Jun-07					
			Qty	Unit	Rate	Total	Qty	Unit	Rate	Total	Qty	Unit	Rate	Total
12		Lift existing basket ball posts out of metal sleeve sockets. Originally bedded in with kln dield sand with 6-9mm clearance in sleeve - recommended removal is by using compressor to blast-out the sand and then to use a hoist to pull and lift post out of sleeve socket) (Posts to be re-installed into new sleeves in Q52)	158.0	Lm	£13.90	£2,196.20	158.0	Lm	£13.90	£2,196.20	79.0	Lm	£13.80	£1,098.10
13		Clearance of existing chainlink fencing and concrete posts. Remove anstings off site to a licensed waste transfer facility (Certificates will be required). Backfill holes and make good existing bitmac surfaces where appropriate with 100mm HA Type 1 and bitmac as Q22/125A.	59.0	Mcb	£9.15	£539.85	59.0	Mcb	£9.15	£539.85	59.0	Mcb	£9.15	£539.85
14		Provisional :: Excavate to reduce levels maximum depth not exceeding 0.25m. Excavate trench 0.6m deep by 0.45m wide for french drain.	23	Mcb	£10.50	£241.50	23	Mcb	£10.50	£241.50	23	Mcb	£10.50	£241.50
15		Dispose of excavated material off site to licensed waste transfer facility. (Waste Transfer Certificates will be required).	82	Mcb	£18.95	£1,553.90	82	Mcb	£18.95	£1,553.90	82	Mcb	£18.95	£1,553.90
16		500; 710. Supply spread and compact fill to bring up levels in MUGA.	7	Mcb	£9.50	£66.50	0	Mcb	£9.50	£0.00	0	Mcb	£9.50	£0.00
17		Purcuture existing bitmac to allow drainage through existing surface at 1m intervals and to a depth of 0.5m.	378	Msq	£0.50	£189.00	0	Msq	£0.50	£0.00	0	Msq	£0.50	£0.00
N FURNITURE / EQUIPMENT														
N14 General Signage Systems														
18		130A; Provisional :: Supply and install site signage. 420A 1000x1000mm screenprinted on aluminium sign on galvanised steel poles sized and installed as recommended by signage manufacturer.	2	Nr	£400.00	£800.00	2	Nr	£400.00	£800.00	0	Nr	£400.00	£0.00
Q PAVING / PLANTING / FENCING/ FURNITURE														
Q10 Kerbedgings/channels														
19		The Contractor shall make allowances in the rates and prices for all necessary cutting, fitting of kerbs to the required radius, fitting against other features and the like and laying in accordance with manufacturer's instruction.												
20		110 Supply and lay BS7263 EF Flat Top kerb 200x50x915mm on GEN 0 concrete, as Dwg. 10607/2248/04 Detail Q3 & Q4	84	Lm	£12.50	£1,050.00	84	Lm	£12.50	£1,050.00	25	Lm	£12.50	£315.00

GROUNDWORK TAMESIDE

20/07/2007

Victoria Park BS4S MUGA

SCHEDULE OF WORKS

Contractor name: **Urban Progress**

Item Clause	Section / Description	25-Apr-07			10-Jul-07			29-Jun-07						
		Qty	Unit	Rate	Total	Qty	Unit	Rate	Total	Qty	Unit	Rate	Total	
21	112	Supply and lay BS7263 CD dished channel on GEN 0 concrete; as Dwg:0807/2248/02 Detail 04.	32	Lm	£16.13	£516.16	32	Lm	£16.13	£516.16	10	Lm	£16.13	£154.85
22	112	Supply and lay BS7263 CSI square channel on GEN 0 concrete; as Dwg:0807/2248/02 Detail 05.	13	Lm	£16.13	£209.69	13	Lm	£16.13	£209.69	4	Lm	£16.13	£62.91
Q20 Granular sub bases to roads/pavings														
23	130	Supply and apply herbicide Casaron G or equivalent approved to subgrade or rolled stone path. <i>State here proposed herbicide manufacturer.</i> <i>State here proposed herbicide name.</i> <i>State here proposed herbicide spreading rate.</i>	1567	Msq	£0.12	£188.04	1567	Msq	£0.12	£188.04	1567	Msq	£0.12	£188.04
24	170	Supply and lay Terran 1000 or equivalent approved geotextile as Dwg:0807/2248/04 Detail 3 & 4.	1567	Msq	£0.45	£705.15	1567	Msq	£0.45	£705.15	1567	Msq	£0.45	£705.15
25	140; 211; 250; Q22; 125A	Supply and lay granular sub-base to 150mm depth as Dwg:0807/2248/02. Include for the compaction of the subgrade and laying to a cross fall of 1:50.	55	Msq	£6.25	£343.75	55	Msq	£6.25	£343.75	0	Msq	£6.25	£0.00
26	140; 215; 250; Q22/125B	Supply and lay granular NO FINES sub-base to 150mm depth for MUGA as Dwg:0807/2248/02. Include for the compaction of the subgrade and laying to a cross fall of 1:100.	1512	Msq	£5.55	£8,391.60	1512	Msq	£5.55	£8,391.60	1512	Msq	£5.55	£8,391.60
Q22 Coated Macadam Paving														
<p>Prerequisite: the prices for all in situ finishes to roads and footpaths include for work to falls, cross falls or slopes not exceeding 15 degrees from the horizontal, for laying on prepared bases and for rolling with an appropriate roller to BS4987.</p>														
27	125A	Supply and lay to footpaths two coat macadam, as Dwg:0807/2248/04 Detail 4 with a crossfall of 1:50.	55	Msq	£14.00	£770.00	55	Msq	£14.00	£770.00	0	Msq	£14.00	£0.00
28	125B	Supply and lay binder course porous bitumen macadam to MUGA Dwg:0807/2248/04 Detail 3 with a crossfall of 1:100.	1512	Msq	£6.50	£9,828.00	1512	Msq	£6.50	£9,828.00	0	Msq	£6.50	£0.00
Q26 Special Surfacings / Pavings for Sport														

Victoria Park BS4S MUCA

SCHEDULE OF WORKS

Contractor name: **Urban Progress**

25-Apr-07

10-Jul-07

29-Jun-07

Item	Section / Clause	Description	25-Apr-07			10-Jul-07			29-Jun-07					
			Qty	Unit	Rate	Total	Qty	Unit	Rate	Total	Qty	Unit	Rate	Total
29	130A: Q22/125B	Supply and lay (Barston Leisuretex / Tarmac Courmaster or equivalent approved) red pigment and hard red aggregate porous macadam with a cross fall of 1:100 as Dwg:0607/2248/03 & 04 Detail 3.	1	Item	£9,436.56	£9,436.56	1	Item	£9,436.56	£9,436.56	0	Item	£9,436.56	£0.00
30	420	Supply and lay thermoplastic sports play markings 50mm wide: Tennis Orange court - Tennis Orange markings in white; Football cage - football markings in white and Tennis Orange markings in yellow; Basketball court - basketball markings in white.	524	Lm	£1.00	£524.00	524	Lm	£1.00	£524.00	0	Lm	£1.00	£0.00
OS2 Play and Sports Equipment Systems														
31	310, 590A	Supply and install multi use games area as attached Dwg:0607/2248/03 & 04 and install as manufacturers instructions. Located as Dwg:0607/2248/03.	1	Item	£26,853.15	£26,853.15	1	Item	£26,853.15	£26,853.15	0	Item	£26,853.15	£0.00
32	520A	Fix only basketball posts, as removed in D20 and placed in site store. Supply and install into new metal sleeves into concrete as instructions of Basketball England - Outdoor Basketball Initiative - 0114 257 7211. Sleeves available from: Carr of Nottingham Ltd - 0115 942 2252 or Rarsome Sporting Goods Ltd - 01642 224444. An installation instruction sheet is included in the tender pack.	1	Item	£255.00	£255.00	1	Item	£255.00	£255.00	0	Item	£255.00	£0.00
33	580	Supply and install football goals: Ø7mm Socketed Steel Anti-Vandal Twist and Lock; 3.6x1.83m; Galvanized to BS EN ISO 1461 and powder coated RAL 9010 Pure White; available from Isa Goal Ltd (0114 243 4200). If alternative is being proposed supply details with tender which demonstrates compliance with required quality standards.	1	Item	£826.00	£826.00	1	Item	£826.00	£826.00	0	Item	£826.00	£0.00
34	640	Supply and install permanent metal tennis net; as Dwg:0607/2248/04 Detail 05 or to approval. If alternative being proposed supply details with tender which demonstrates compliance with required quality standards.	1	Item	£1,668.00	£1,668.00	1	Item	£1,668.00	£1,668.00	0	Item	£1,668.00	£0.00
R DISPOSAL SYSTEMS														
R12 Drainage below ground														

GROUNDWORK TAMESIDE

20/07/2007

Page 4 of 6

Victoria Park BS4S MUGA

SCHEDULE OF WORKS

Contractor name: **Urban Progress**

25-Apr-07

10-Jul-07

29-Jun-07

Item	Section / Clause	Description	Qty	Unit	Rate	Total
35	14; 27.	Provisional :: Supply and lay 110mm Hepworth PlastDrain, include for minimum 150mm mastic concrete surround laid on bed of 100mm pea gravel, as shown on Dwg:0607/2248/02 and removal of arisings off site to a licensed waste transfer facility. Make good bitmac surfaces disturbed by excavations. (This would replace existing drainage pipe linking to all new drains should the existing pipe be found to be beyond economical use and or repair)	500	Lm	€35.00	€1,750.00
35	50A	Supply and fit trapped gully, include for excavations, foundations, removal of spoil of site to a licensed waste transfer facility, connection to 110mm Hepworth PlastDrain pipe and 285x265mm medium duty iron hinged dischd yard gully grating and frame with allen key locking facility (Peter Savage Ltd 01924 258 381 product: KD71/LA). Located as Dwg:0506/2248/02.	5	Nr	€375.00	€1,875.00
36	61A; 79	Provisional :: Connect to existing drainage system. Inclusive of excavations, foundations; removal of arisings off site; and construction of manhole at junction with existing drain with 600x600mm C250 Heavy Duty iron manhole cover.	1	Nr	€500.00	€500.00
R13 Land Drainage						
37	211	Supply and construct french drain with Terram 1000 wrap into trench measured elsewhere, as Dwg:0607/2248/02 Detail 02 & 03.	132	Lm	€11.50	€1,518.00
38	600A; 640.	Supply and install silt trap / inspection chamber at intersections and changes in direction of French drains, inclusive of excavations, foundations; removal of arisings off site; and with a 600x600mm C250 Heavy Duty iron manhole cover.	2	Nr	€495.00	€990.00
Extra Items						
		Additional excavations	0			€0.00
		Laying and consolidating fill	0			€0.00
		Removal of additional fill from site	0			€0.00
		Excavation for initial investigation	0			€0.00
		Hire of pump	0			€0.00
		Diesel	0			€0.00
		Labour to man pump	0			€0.00
		Rodding of drain	0			€0.00

Qty	Unit	Rate	Total
500	Lm	€35.00	€1,750.00
5	Nr	€375.00	€1,875.00
1	Nr	€500.00	€500.00
132	Lm	€11.50	€1,518.00
2	Nr	€495.00	€990.00
0			€0.00
0			€0.00
0			€0.00
0			€0.00
0			€0.00
0			€0.00
0			€0.00
0			€0.00

Qty	Unit	Rate	Total
0	Lm	€35.00	€0.00
5	Nr	€375.00	€1,875.00
1	Nr	€500.00	€500.00
132	Lm	€11.50	€1,518.00
2	Nr	€495.00	€990.00
0			€497.76
0			€516.50
0			€1,137.00
0			€78.50
0			€75.00
0			€15.00
0			€394.56
0			€197.28

Qty	Unit	Rate	Total
0	Lm	€35.00	€0.00
2	Nr	€375.00	€750.00
1	Nr	€500.00	€500.00
132	Lm	€11.50	€1,518.00
1	Nr	€495.00	€495.00
0			€497.76
0			€316.50
0			€1,137.00
0			€78.50
0			€75.00
0			€15.00
0			€394.56
0			€197.28

GROUNDWORK TAKESIDE

20/07/2007

Page 5 of 6

Victoria park court project file

Carol Redfern

From: Nick.Linder@groundwork.org.uk
Sent: 17 April 2007 11:34
To: Andy Cush
Cc: Stuart Mollison
Subject: Planning Application Victoria park, Denton 06/00744/R3D
Attachments: Contract drawing 20070417 MUGA LAYOUT.pdf; Contract drawing 20070417 MUGA CONSTRUCTION.pdf

Hello Andy,

Condition 2 of planning approval Victoria park, Denton 06/00744/R3D requires that we submit the proposed colours for the fencing for you to agree before we commence work on site.

The attached drawing show the proposed colours for fencing. Please note the design of the scheme has changed slightly as we feel we have found better way of providing DDA access to the courts.

Nick Linder
Landscape Architect
Land Team

Groundwork Tameside
Birchcroft
Crowthorne Road
ASHTON UNDER LYNE
OL7 0DH


Direct line :: 0161 342 6732
Main fax :: 0161 342 6768

www.tameside.groundworknw.org.uk

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed. It may contain privileged and confidential information. If you have received this message in error or there are any problems, please notify the sender immediately and delete the message from your computer. The unauthorised use, disclosure, copying or alteration of this message is forbidden. Groundwork Tameside will not be liable for direct, special, indirect or consequential damage as a result of any virus being passed on, or arising from alteration of the contents of this message by a third party.

The views expressed in this e-mail do not necessarily represent the views of Groundwork Tameside or the Federation of Groundwork Trusts.

18/04/2007



© 2007 CONCRETEWORK TAMESIDE
 No part of this document may be reproduced without the written permission of the author.

Drawings to be checked against previous drawings.

- TERNS ORANGE AND BASKETBALL WALLS:** USE EXISTING OR EQUIVALENT WELDED MESH WIRE. COLOURS: ALL PANELS BLUE RAL 5015. ALL POSTS YELLOW RAL 1023.
- FOOTBALL END WALLS (HIGHER LOWER TERNS TO 2.1M HIGH):** USE EXISTING OR EQUIVALENT WELDED MESH WIRE. COLOURS: ALL PANELS BLUE RAL 5015. ALL POSTS YELLOW RAL 1023.
- FOOTBALL END WALLS (LOWER TERNS TO 2.1M HIGH):** USE EXISTING OR EQUIVALENT WELDED MESH WIRE. COLOURS: ALL PANELS BLUE RAL 5015. ALL POSTS YELLOW RAL 1023.

REVISIONS
 STATES PROPOSED COLOURS OF FENCING
 SHOWS PROPOSED CHANGES TO THE HAZING HEIGHT OF THE TERNS TO THE EDGE OF THE FOOTBALL GOAL
 SHOWS THE PROPOSED CHANGES TO THE WALLS OF FOOTBALL GOALS

THESE DIMENSIONS TO BE CONFIRMED BY SITE MEASUREMENT AND LIAISON WITH CA

Project: VICTORIA PARK BS45 MUGA
Design: MUGA LAYOUT
Drawn: 04/22/07/03 **Checked:** AA
Date: 04/20/07 **Quantity:** 1/1
Scale: 1:100 **Revised:** A
Printed:



© 2007 GROUNDWORK TAMESIDE
 No part of this document may be reproduced by any means without prior written permission.
 Drawn by: M. Deakin (0961606963) (m.d.)
 P. M. COOPER A.S.K.



Notes:

FOOTBALL SIDE WALLS 3M HIGH LOWER SECTION TO 1.2M HIGH OF HEAVY DUTY DOUBLE WIRE REBOUND AND UPPER SECTION OF IAE DUEX 889 OR EQUIVALENT APPROVED WELDMESH TO GIVE A TOTAL HEIGHT OF 3M. COLOURS: ALL PANELS BLUE RAL 5010 ALL POSTS YELLOW RAL 1023

FOOTBALL END WALLS 4M HIGH LOWER SECTION TO 2.0M HIGH OF HEAVY DUTY DOUBLE WIRE REBOUND AND UPPER SECTION OF IAE DUEX 889 OR EQUIVALENT APPROVED WELDMESH TO GIVE A TOTAL HEIGHT OF 4M. COLOURS: ALL PANELS BLUE RAL 5010 ALL POSTS YELLOW RAL 1023

TENNIS ORANGE AND BASKETBALL WALLS: IAE DUEX 889 (OR EQUIVALENT APPROVED) DOUBLE WIRE WELDMESH 3M HIGH. COLOURS: ALL PANELS BLUE RAL 5010 ALL POSTS YELLOW RAL 1023


TENNIS NET COLOURS: ALL PANELS YELLOW RAL 1023 WITH POSTS AND TOP RAIL WHITE RAL 9010

SET BACK PANELS AT ENTRANCES, POSTS AND PANELS TO BE RED RAL 3000.


REVISION A
 STATES PROPOSED COLOURS OF FENCING
 SHOWS PROPOSED CHANGES TO THE FENCING HEIGHT OF THE FENCING TO THE SIDES OF THE FOOTBALL COURT
 SHOWS THE PROPOSED CHANGES TO THE MAKE UP OF FOOTBALL END WALLS

Project: VICTORIA PARK BS45 MUGA
 Drawing: MUGA CONSTRUCTION
 Drawing No: 0.607/22/48/04
 Date: 04/2007
 Drawn by: AA
 Checked by: NL
 Scale: AS SHOWN
 Revision: A


GROUNDWORK Tameside
 (aerial) Groundwork
 Cowthorpe Road
 Ashton Under Lyne
 OL7 7QH
 161 661 342 6767 Fax: 0161 946 0788




DETAIL 01 :: MUGA SIDE WALL ELEVATION
 SCALE 1:100




DETAIL 02a :: MUGA END WALL ELEVATION
 SCALE 1:100



DETAIL 02b :: MUGA END WALL ELEVATION
 SCALE 1:100



DETAIL 05 :: MUGA PERMANENT TENNIS NET
 SCALE 1:50



DETAIL 04 :: PCC EDGE - BITMAC TO GRASS DETAIL
 SCALE 1:10

DETAIL 03 :: PCC EDGE - BITMAC TO BITMAC DETAIL
 SCALE 1:10